

August 7, 2018 Client Number 4844 Report Number 10139

No. 2560

Channel Islands Beach Community Services District 353 Santa Monica Drive Oxnard, CA 93035

Feasibility Level Geotechnical Engineering Study
Future Single-Family Residence
112 Las Palmas Street
Oxnard, California

In accordance with our proposal and your authorization, Advanced Geotechnical Services, Inc., (AGS) has prepared this *Feasibility Level Geotechnical Engineering Study* for the construction of a future single-family residence at the subject site. This report presents the results of our data research, subsurface exploration, laboratory testing, and our professional opinions regarding the geotechnical engineering factors that may affect the future development.

Based on the results of our study, it is our opinion that the site is suitable for construction of the future single-family residence and associated improvements, provided recommendations of this report are properly incorporated in the design and implemented during construction.

This opportunity to be of service is sincerely appreciated. This report should be read from cover to cover to understand its limitations and to avoid taking any recommendations out-of-context. If you have any questions, or if we may be of any further assistance, please do *not* hesitate to call. We look forward to being of continued service.

Scott Moore, GE

Principal Engineer

Respectfully submitted,

Advanced Geotechnical Services, Inc.

Kenneth J. Palos

President

Enclosure: Report No. 10139

cc: (5) Addressee (1) File Copy



# FEASIBILITY LEVEL GEOTECHNICAL ENGINEERING STUDY

Future Single-Family Residence 112 Las Palmas Street Oxnard, California

Report to
Channel Islands Beach Community Services District
353 Santa Monica Drive
Oxnard, California

August 7, 2018 Client Number 4844 Report Number 10139



# **Contents**

1.	INTR	ODUCTION	1
	1.1	General Remarks	1
	1.2	Site Description and Future Development	1
	1.3	Scope of Services	1
2.		LOGIC SETTING	
4.			
	2.1	Geology	
	2.2	Faulting	2
3.	EAR	TH MATERIALS AND SUBSURFACE CONDITIONS	2
	3.1	Earth Materials	2
	3.2	Existing Abandoned Well	3
	3.3	Soil Parameters	3
	3.3.1	Maximum Density	
	3.3.2	Expansion Category	
	3.3.3	Compressibility	
	3.3.4	Shear Strength	
	3.3.5	Corrosivity	4
	3.4	Groundwater	4
4.	SEIS	MICITY	4
	4.1	Seismic Design Criteria	4
	4.2	Earthquake Effects	
	4.2.1	Shallow Ground Rupture	
	4.2.2	Earthquake-Induced Landsliding	
	4.2.3	Seiches and Tsunamis	
	4.2.4	Evaluation of Liquefaction Potential	
	4.2.5	Dynamic Dry Settlement	
5.	CON	CLUSIONS AND RECOMMENDATIONS	7
	5.1	Conclusions and Design Requirements	7
	5.1.1	Faults / Seismicity	7
	5.1.2	Hazardous Materials	
	5.1.3	Site Grade Adjustments	
	5.1.4	Excavation Characteristics	
	5.1.5	Drainage	
	5.1.6 5.1.7	Plan ReviewAdditional Recommendations	
	5.2	Site Preparation	
	5.2.1	Removals	
	5.2.2	Bottom Stabilization	
	5.2.3	Suitable Fill Material	
	5.2.4	Placement of Compacted Fill	
	5.2.5 5.2.6	Testing of Compacted Fill	
	5.2.7	Responsibilities	
		·	
	5.3	Utility Trench Backfill	
	5.4	Temporary Excavations	12



	5.5	Foundation Design	12
	5.5.1	Allowable Bearing Pressure and Lateral Resistance	12
	5.5.2	Foundation Settlement	13
	5.5.3	Steel Reinforcement	13
	5 5 4	Required Observations	13
	5.5.5	Vapor Barrier	13
	5.6	Concrete Pavement and Patio Design	13
6.	OBSE	ERVATIONS AND TESTING	13
7.	LIMI	TS AND LIABILITY	14

# **List of Appendices**

- A Field Exploration and Boring Logs
- B Laboratory Testing
- C Seismicity Study
- D Liquefaction Evaluation
- E References
- F Well Abandonment Documentation
- G Report Figures
  - 1 Site Location Map
  - 2 Existing Site Plan
  - 3 Depth to Historically High Groundwater
  - 4 Seismic Hazard Zones Map



#### 1. INTRODUCTION

#### 1.1 General Remarks

This Feasibility Level Geotechnical Engineering Study has been prepared for the construction of a future single-family residence at the subject site. The purposes of this study are to (1) identify on-site soil conditions, (2) evaluate potential seismic hazards at the site, and (3) provide feasibility level geotechnical recommendations to be utilized in the design and construction of the future single-family residence, and other associated improvements. This report presents the findings of our data review, subsurface exploration, laboratory testing, engineering analyses and evaluations, and our conclusions and recommendations.

Appendices are attached following the main report. Appendix A includes an explanation of the field exploration, and boring logs; Appendix B includes the laboratory test results; Appendix C includes the results of the seismicity study; Appendix D includes the results of the site liquefaction analysis; Appendix E includes the references used in this study; Appendix F includes the documentation regarding the previously existing water well abandonment, and Appendix G includes the Figures referenced in this report.

# 1.2 Site Description and Future Development

The subject site is located at 112 Las Palmas Street, in the Oxnard area of Ventura County, California. A *Site Location Map* is provided as Figure 1, and an *Existing Site Plan* is provided as Figure 2, both based on images obtained from the Google Earth web app (2018). The subject site consists of a relatively flat, rectangular shaped parcel, elevated up to a few feet above the adjacent Las Palmas Street level.

At the time of our field exploration program, the subject site was vacant, with scattered vegetation consisting of ice plant and weeds. The site is bounded by Las Palmas Street to the north, and existing residential properties to the east, south and west.

The future development will consist of a new single-family residence, and the typical associated site improvements, including site flatwork such as driveways and walkways. Plans of the proposed future residence are not yet available, however it is likely that the future residence will have the same front, rear and side yard setbacks as the neighboring residences, and will be constructed at or near the current existing grade in the central portion of the property. It is anticipated that the future single-family residence will be a typical wood-framed structure, with maximum loads not expected to exceed approximately 50 kips for columns, and 1 to 2 kips per foot for walls.

Plans of the future development were not available as of the date of this report, however site grading is expected to consist of removal and recompaction of the upper site soils, and the existing artificial fill associated with the abandonment of the previously existing water well, for support of the future structure and other improvements, and backfill of new utilities. Only minor alterations to the site topography of less than approximately 1 to 2 feet are anticipated.

#### 1.3 Scope of Services

This feasibility level geotechnical engineering study included:

- a. Site observation and review of geotechnical and geologic data of the general study area. A *Site Location Map* is provided as Figure 1, and an *Existing Site Plan* is provided as Figure 2, both based on images from the Google Earth web app (2018).
- b. Drilling, sampling, and logging of two borings to depths between approximately 16.5 and 51.5 feet below the existing ground surface for soils evaluation. The exploratory borings were located in the field using a tape measure and approximate reference points. Thus, the actual locations of the exploratory borings may deviate slightly from the locations shown on



the attached Figure 2. The Boring Logs are included in Appendix A, along with a general description of the field operations.

- c. Laboratory testing of selected samples to determine the engineering properties of on-site soils. The results of laboratory testing are presented in Appendix B and on the boring logs in Appendix A. Soil samples will be *discarded* 30 days after the date of this report, unless this office receives a specific request and fee to retain the samples for a longer period of time.
- d. Determination of seismic parameters for potential on-site ground motion.
- e. Engineering analysis of the data and information obtained from our field study, laboratory testing, and literature review.
- f. Development of feasibility level geotechnical recommendations for site preparation and grading, and geotechnical design criteria for foundations, floor slabs, site flatwork, underground utility trenches, temporary excavations, and drainage.
- g. Preparation of this report summarizing our findings, conclusions, and recommendations regarding the geotechnical aspects of the project site.

The scope of this feasibility level geotechnical study did *not* include environmental issues.

#### 2. GEOLOGIC SETTING

#### 2.1 Geology

Geologic conditions beneath the subject property have been interpreted and characterized based upon our review of published and unpublished references, and our subsurface exploration. Our interpretations involve projections of data and assume that geologic conditions are reasonably constant between points of exposure. Work should continue under the review of the Geotechnical Engineer to ensure that geologic conditions different from those described below are recognized and evaluated as soon as possible. Certain subsurface conditions such as groundwater levels and the consistency of near-surface soils will vary with the seasons. The subject site is located within the Oxnard USGS 7.5-minute quadrangle.

# 2.2 Faulting

Southern California is a tectonically active region subject to hazards associated with earthquakes and faulting. Faults are classified as either active, potentially active, or inactive. Active faults are defined by the State of California as faults that have exhibited surface displacement within the last 11,000 years. Potentially active faults are defined by the State of California as those with a history of movement between 11,000 and 1.6 million years ago.

Alquist-Priolo Earthquake Fault Zones are zones that have been established by the State that contain active faults, and projects that are located within these zones require that a fault investigation be performed to determine if active faulting affects the site. Other undiscovered active faults without surface expression, called blind faults, are also capable of generating earthquakes, and may be present beneath the subject site. The site is *not* located in an Alquist-Priolo Earthquake Fault Zone, and therefore a detailed subsurface fault investigation is not required.

#### 3. EARTH MATERIALS AND SUBSURFACE CONDITIONS

#### 3.1 Earth Materials

The earth materials encountered during exploration from the ground surface to a depth of approximately 40 feet consist of beach sand (Qs), likely interlayered with sandy alluvial deposits at depth. At a depth of 40 feet, a stiff sandy silt with minor clay was encountered, which continued to the total depth explored, 51.5 feet. The beach sand



is relatively dry and loose at the ground surface, and becomes moderately dense and slightly moist by a depth of approximately 1 to 2 feet, and generally increasingly moist with depth. The sand becomes wet at a depth of 8.5 to 9 feet, where groundwater was encountered. The sand is tan to light gray, and ranges from moderately dense to dense below a depth of 1 to 2 feet. The sandy silt at a depth of 40 feet is light gray, fine grained, very moist and stiff. More detailed descriptions of the earth materials encountered can be found on the enclosed boring logs.

# 3.2 Existing Abandoned Well

There was a previously existing water well on the subject site that was abandoned in 2003. Based on the well abandonment documents provided to us by our client (included in Appendix F), there is no information available regarding the exact location of the abandoned well, or the exact depth and lateral extent of the excavation made during the abandonment of the well. The location of the abandoned well can only be approximately inferred from the photographs included with the well abandonment documents. The 'Conditions for Well Destruction' contained on the *Well Permit Application*, dated 1/28/03, indicates that the well casing was to be filled with cement from the bottom of the well up to a depth of 5 feet below finish grade, and the well casing above that was to be removed. Therefore, the minimum depth of uncertified fill placed back into the well abandonment excavation is likely 5 feet ('uncertified fill' being any man-made fill that was not inspected, tested, and certified by a geotechnical engineering company). The lateral extent of the uncertified fill is unknown however.

All of the uncertified fill resulting from the well abandonment will have to be removed, stockpiled onsite, and then properly compacted back into the resulting excavation, under the observation and testing of a geotechnical engineering company. A qualified representative of a geotechnical engineering company would be onsite during the excavation process to help determine the depth and lateral extent of the existing uncertified fill, which is mainly a visual determination.

#### 3.3 Soil Parameters

#### 3.3.1 Maximum Density

A compaction curve was developed in this study for a sample of the beach sand material between the depths of approximately 0 and 5 feet. The maximum dry density for this material was 106.5 pcf, at an optimum moisture content of 13.5%. This value may be utilized as a guideline during the required removal and recompaction of the upper onsite soils during grading.

#### 3.3.2 Expansion Category

The potential of the soil to swell or expand increases with an increase in soil density, a decrease in initial moisture content (low percent saturation), an increase in clay content, and an increase in the activity of the clay content. Expansive soils change in volume (shrink or swell) due to changes in the soil moisture content. In addition to swell potential of the soil, the amount of volume change depends on (1) the availability of water, (2) the restraining pressure, and (3) time. The risk of soil expansion increases with an increase in expansion index. These test results show that the upper site soils are non-expansive (therefore in the *very low* expansion range, with an expansion index of 0).

#### 3.3.3 Compressibility

A consolidation test was performed on a representative undisturbed sample of the onsite soils from a depth of 5 feet below the existing ground surface. The consolidation test results showed only a slight tendency to hydroconsolidate, and a relatively low potential of compressibility. Consolidation test results are included in Appendix B.

#### 3.3.4 Shear Strength

Direct shear testing was used to measure the peak and ultimate shear strength properties of representative samples of the onsite soils, both remolded and undisturbed, in terms of a cohesion value and a friction angle. The results of the direct shear testing are presented in Appendix B of this report.



# 3.3.5 Corrosivity

The risk of corrosion of construction materials relates to the potential for soil-induced chemical reaction. The rate of deterioration depends on soil resistivity, texture, acidity, and chemical concentration. To provide a basis for a preliminary corrosion evaluation, one sample of the near surface soils on the site was analyzed. The results of these tests are summarized in the following table, and the test results data sheet from American Analytics is attached in Appendix B. Sulfate and chloride concentrations are expressed in mg/kg on a dry weight basis.

Boring	Depth, Ft	Description	рН	Chloride, mg/kg	Sulfate, mg/kg	Specific Conductance, umhos/cm
B-1	0-5	Sand	7.5	22	16	270

The sulfate content is below 1000 mg/kg (S0 exposure category based on ACI 318), and therefore special considerations for concrete which will be in contact with the onsite soils are not required.

#### 3.4 Groundwater

At the time of our field exploration, groundwater was encountered at a depth of approximately 8.5 to 9 feet below the existing ground surface. Based on the *Depth to Historically High Groundwater* Map (CGS, 2002), Figure 3, the historically highest groundwater level in the site vicinity was approximately 5 feet below the existing ground surface. Groundwater elevations are dependent on seasonal precipitation, irrigation, land use, climatic conditions, among other factors, and as a result fluctuate. Therefore, water levels at the time of construction and during the life of the structure may vary from the observations or conditions at the time of our field exploration.

#### 4. SEISMICITY

# 4.1 Seismic Design Criteria

The 2016 CBC specifies the use of the *Mapped Maximum Considered Geometric Mean (MCEG) Peak Ground Acceleration, PGA*, which is adjusted for site class effects to obtain PGA<sub>M</sub>. For the subject site, PGA and PGA<sub>M</sub> are both 0.768g, as indicated on page 5 of the *USGS Design Maps Detailed Report* included as an attachment in Appendix C of this report.

The 2016 California Building Code (CBC) is utilized in the seismic design of structures, and is based on the *Maximum Considered Earthquake Ground Motion*. The earth materials underlying the site are classified based on parameters such as shear wave velocity, standard penetration test resistance, undrained shear strength, and earth material type. The maximum considered earthquake spectral response accelerations are then adjusted for general type of earth materials underlying the site, or *Site Class*, which would be D for the subject site. The remaining seismic parameters used in structural analyses are computed by the Structural Engineer from the values shown below.

The following seismic design coefficients and parameters for the project site have been determined utilizing the U.S. Seismic Design Maps web program developed by the United States Geological Survey (2014). The program incorporates seismic provisions set forth in the 2016 California Building Code (CBC) and 2015 International Building Code (IBC) procedures. Printout data generated by the USGS program is included in Appendix C of this report for reference.

Site Class	Spectral Accelerations, 0.2-Second Period, Ss	Spectral Accelerations, 1-Second Period, S <sub>1</sub>	Site Coefficient, F <sub>a</sub>	Site Coefficient, F <sub>v</sub>	Adjusted Spectral Accelerations, 0.2-Second Period, S <sub>MS</sub>	Adjusted Spectral Accelerations, 1-Second Period, S <sub>M1</sub>	Adjusted Spectral Accelerations, 0.2-Second Period, Sps	Adjusted Spectral Accelerations, 1-Second Period, Sp1
D	2.053	0.727	1.0	1.5	2.053	1.090	1.369	0.727



Conformance to these criteria does *not* constitute a guarantee or assurance that significant structural damage or ground failure will *not* occur if a maximum level earthquake occurs. The primary goal of seismic design is to protect life and *not* to avoid all damage, since such design may be economically prohibitive.

# 4.2 Earthquake Effects

The intensity of ground shaking during an earthquake can result in a number of phenomena classified as ground failure, which include ground rupture due to faulting, landslides, liquefaction, lurching, and seismically induced settlement. Other seismic hazards include Seiches and tsunamis. Descriptions of each of these phenomena and an assessment of each, as it may affect the future development, are included in the following sections. The Seismic Hazards Mapping Act of 1990, which became effective in 1991, requires mitigation of seismic hazards to a level that does *not* cause collapse of the building intended for human occupancy, but it does *not* require mitigation to a level of no ground failure or structural damage.

#### 4.2.1 Shallow Ground Rupture

Ground surface rupture occurs when movement along a fault is sufficient to cause a gap or rupture where the upper edge of the fault zone intersects the ground surface. Where associated with reverse faults, such ruptures rarely occur as single breaks or are confined to a narrow zone. More commonly, ground rupture associated with faulting is characterized by relatively short segments of faulting that occur over a broad area of the upper plate. In some cases, particularly in unconsolidated alluvial sediments, *secondary ground ruptures* can develop from a number of causes not necessarily related directly to surface rupture of the causative fault. The secondary effects may include seismic settlement, landslides, and liquefaction.

Since there are *no* known active or potentially active surface fault traces passing through the site, the potential for on-site ground rupture due to movement on an underlying fault in *not* considered a significant hazard, although it is a possibility at any site. The potential for ground rupture due to other causes is discussed in the following sections.

#### 4.2.2 Earthquake-Induced Landsliding

Landslides are slope failures that occur where the horizontal seismic forces act to induce soil failure. Seismic Hazard Maps have been released by the California Geological Survey that delineate areas that have been subject to, or are potentially subject to landsliding or permanent ground displacement as a result of earthquake-induced ground shaking. Since the site and surrounding area are relatively flat, on-site earthquake-induced landsliding is not considered to be a hazard. The site is not located in an area designated on the Seismic Hazard Zones Map (CGS, 2002), Figure 4, as being susceptible to hazards associated with earthquake-induced landslides.

#### 4.2.3 Seiches and Tsunamis

Seiches are an oscillation of the surface of an inland body of water that varies in period from a few minutes to several hours. Seismic ground motions can induce such oscillations. Tsunamis are large sea waves produced by submarine earthquakes or volcanic eruptions. The site is *not* located close to an inland body of water, but the site is located within an area designated on the Ventura County Seismic Risk Maps as being at risk for tsunami runup.

#### 4.2.4 Evaluation of Liquefaction Potential

Liquefaction is a phenomenon in which soils below the groundwater level lose strength as a result of ground shaking due to earthquakes. The site is located in an area designated as potentially liquefiable on the *Seismic Hazard Zones Map* of the Oxnard Quadrangle (CDMG 2002), Figure 4. The results of field exploration and laboratory testing conducted as part of this investigation indicate that the subject site meets the criteria of being potentially susceptible to liquefaction. A detailed liquefaction analysis was therefore performed to further evaluate the potential and extent of possible liquefaction at this site.

Exploratory Boring B-1 was excavated to a depth of 51.5 feet to assess the liquefaction hazard potential at the site. The geotechnical data obtained from the boring and our laboratory test results, including standard



penetration test data (SPT), percent fines and clay fraction, were utilized in our evaluation of liquefaction hazard potential at the site. Beach sand likely interlayered with alluvial sand deposits were encountered from the ground surface to a depth of approximately 40 feet, followed by sandy silt to the total depth explored, 51.5 feet

At the time of our field exploration, groundwater was encountered and stabilized at a depth of approximately 9 feet below the existing ground surface in Boring B-1. Based on the *Depth to Historically High Groundwater* Map (CGS, 2002), Figure 3, the historically highest groundwater level below the existing ground surface at the site is approximately 5 feet. The liquefaction hazard analysis was therefore performed utilizing the historically highest groundwater level of 5 feet below the ground surface.

The methods following the recommendations of the NCEER (Youd and Idriss, 1997; Youd et al, 2001) were used in the liquefaction analysis, supplemented by the recommendations of Bray and Sancio (2006), and Boulanger and Idriss (2006) in the analysis of fine grained soils (clays and silts). A design-level earthquake magnitude of 6.9, and a site acceleration of 0.768 (PGA<sub>M</sub>) were utilized to perform the liquefaction evaluation.

Blow counts used for the liquefaction evaluation were based on the blow counts measured with an unlined, Standard Penetration Test sampler, or a modified California sampler, utilizing a 140-pound automatic trip hammer, falling 30 inches. The blow counts obtained when utilizing the modified California sampler were then multiplied by a factor of  $^2$ /3 to convert to equivalent SPT blow counts, and then divided by 1.2 to cancel the unlined sample correction factor utilized in the liquefaction analysis spreadsheet. The measured blow counts were further adjusted for borehole diameter, rod length, sampling method and delivered energy (Youd and Idriss, 1997 and 2001) to correspond to a driving-energy level of 60% (N<sub>60</sub>). The adjusted blow counts (N<sub>60</sub>) were then adjusted for overburden pressure to obtain N<sub>1</sub>|<sub>60</sub>.

The results of the liquefaction analysis indicate that there are potentially liquefiable soils between the depths of approximately 7.5 and 15 feet, and 45 and 50 feet below the existing ground surface. Utilizing the procedures of Tokimatsu and Seed (1987), the maximum potential liquefaction induced settlement is anticipated to be approximately 2.35 inches. Potential differential settlement due to liquefaction is typically considered to be up to a maximum of approximately two-thirds of the total settlement, which would be approximately 1.57 inches, and is typically assumed to occur over a span of 30 feet. Therefore, as discussed in subsequent sections of this report, a mat foundation is recommended for support of the future structure. The remainder of the earth materials consist of either moderately dense to dense sand or stiff sandy silt, with corrected SPT blow counts all above 30, and would therefore not be considered susceptible to liquefaction (CGS, 2008).

The subject site is located in a relatively flat to only gently sloping area, with no open channel faces or descending slopes in the immediate vicinity, and the corrected, equivalent SPT blow counts are all above 15. Therefore, the risk of liquefaction-induced lateral spreading is considered to be negligible (Bartlett and Youd, 1992).

Based on the relative thicknesses of non-liquefiable soils overlying potentially liquefiable layers, and the fact that the first potentially liquefiable layer is at a depth of only 7.5, there is the potential for localized loss of bearing capacity, and other surface manifestations of liquefaction such as sand boils and fissures. Therefore, as discussed in subsequent sections of this report, a mat foundation is recommended for support of the future structure.

# 4.2.5 Dynamic Dry Settlement

The upper site soils will be removed and recompacted for support of the future structure, and the existing groundwater level is relatively shallow. Therefore, the potential for any significant dynamic dry settlement of dry sandy soils during seismic shaking is considered to be negligible.



#### 5. CONCLUSIONS AND RECOMMENDATIONS

#### 5.1 Conclusions and Design Requirements

Based on the findings of our data review, subsurface exploration, laboratory testing, field testing, and engineering analysis, and within the scope of this study, the future improvements are considered *feasible* from a geotechnical engineering viewpoint, provided the recommendations in this report are incorporated into the building plans and implemented during construction. The following sections discuss conditions that should be anticipated, and provide specific recommendations for mitigation of adverse conditions during the design and construction phase of improvements.

The upper onsite soils should be removed and properly recompacted for support of the proposed structure and other site improvements, as detailed in the following sections. Within the proposed building area, it is recommended that the existing earth materials be removed and recompacted to a depth of approximately 3 feet below existing and future site grade, and a minimum of 1 foot below the bottom of foundations, whichever is deeper. In the area of the proposed driveways, walkways and other miscellaneous surface improvements, it is recommended that a minimum of approximately 1 foot of newly placed compacted fill be provided for support of these elements.

Due to the presence of potentially liquefiable soils, and the potential for total and differential liquefaction-induced settlements of an estimated 2.35 and 1.57 inches, respectively, and the potential for surface manifestation of liquefaction including sand boils and loss of bearing capacity, it is recommended that a mat foundation be utilized for support of the future structure. It is recommended that the proposed foundation system be supported entirely on newly placed compacted fill.

All uncertified fill associated with the abandonment of the previously existing water well onsite should be removed, stockpiled onsite, and properly recompacted during site grading. A qualified representative of a geotechnical engineering company would be onsite during the excavation process to help determine the depth and lateral extent of the existing uncertified fill, which is mainly a visual determination.

#### 5.1.1 Faults / Seismicity

Although no known active surface fault traces cross the subject site, like most of Southern California, the site lies within a seismically active area. Earthquake resistant structural design is recommended. Designing structures to be earthquake-proof is generally considered to be impractical, especially for private projects, due to cost limitations. Significant damage to structures may be unavoidable during large earthquakes. Structural design based on the 2016 CBC (California Building Code) structural analysis procedures calls for the seismic parameters given previously in the *Seismic Design Criteria* section of this report. These minimum code values are intended to protect life and may not provide an acceptable level of protection against significant cosmetic damage and serious economic loss. Significantly higher than code parameter values would be necessary to further reduce potential economic loss during a major seismic event. Structural Engineers, however, often regard higher than code values or procedures as impractical for use in structural design. The Structural Engineer and project Owner must decide if the level of risk associated with code values is acceptable and, if not, to assign appropriate seismic values above code values for use in structural design.

#### 5.1.2 Hazardous Materials

AGS has *not* been retained to provide any type of environmental assessment of the subject property, nor to provide recommendations with respect to any contamination that might be present.

# 5.1.3 Site Grade Adjustments

Grading for the future single-family residence is expected to consist of removal and recompaction of the existing well abandonment backfill, and the upper site soils for support of the future structure and associated



improvements. The finished building pad elevation is expected to be within approximately 1 to 2 feet of the existing grade at the site.

#### 5.1.4 Excavation Characteristics

The upper earth materials underlying the site consist of sand, and therefore hard to excavate materials should not be encountered. Caving of the sandy soils should be expected.

# 5.1.5 Drainage

All surface runoff must be carefully controlled and must remain a crucial element of site maintenance. Proper drainage and irrigation are important to reduce the potential for excessive infiltration adjacent to foundations. Final grading should provide positive drainage away from footings and other improvements in compliance with the local jurisdiction's grading requirements. All pad drainage shall be collected and diverted away from future structure and foundations in non-erosive devices. Gutters and roof drains should be provided, properly maintained, and discharge directly into glue-joined, watertight subsurface piping. A drainage system consisting of area drains, catch basins, and connecting lines should be provided to capture landscape/hardscape sheet flow discharge water. All drainage piping should be watertight and discharge to an appropriate location, as determined by the project Civil Engineer.

All underground plumbing fixtures should be absolutely leak-free. As part of the maintenance program, utility lines should be checked for leaks for early detection of water infiltrating the soils that could cause detrimental soil movements. Detected leaks should be promptly repaired. Proper drainage shall also be provided away from the building footings during construction. This is especially important when construction takes place during the rainy season.

Seepage of surface irrigation water or the spread of extensive root systems into the subgrade of footings, slabs, concrete flatwork or pavements can cause differential movements and consequent distress in these structural elements. Trees and large shrubbery should *not* be planted so that roots grow under foundations and flatwork when they reach maturity. Landscaping and watering schedules should be planned with consideration for these potential problems.

Drainage systems should be well maintained, and care should be taken to *not over* or *under* irrigate the site. Landscape watering should be held to a minimum while maintaining a uniformly moist condition without allowing the soil to dry out. During extreme hot and dry periods, adequate watering may be necessary to keep soil from separating or pulling back from the foundations. Cracks in paved surfaces should be sealed to limit infiltration of surface waters.

#### 5.1.6 Plan Review

When final Building and Grading Plans become available, they should be reviewed by AGS *prior* to submittal to regulatory agencies for approval. An update geotechnical report will be required when plans become available, and additional analysis *may* be required at that time depending on specific details of the proposed grading and improvements. Approval by this office will be indicated on the plans by *manual* signature and stamp.

Please be aware that the contract fee for our services to prepare this report does not include additional work that may be required, such as grading observation and testing, footing observations, plan review, or responses to governmental (regulatory) plan reviews associated with you obtaining a building permit. Where additional services are requested or required, you will be billed on an hourly basis for consultation or analysis. AGS requests a minimum of 24 hours be provided for plan reviews. Please anticipate additional time for plan corrections if all of our geotechnical recommendations have not been added to the plans, prior to our approving and stamping the plans.



#### 5.1.7 Additional Recommendations

The following additional feasibility level geotechnical recommendations should be incorporated into the final design and construction plans. All such work and design should be in conformance with local governmental regulations or the recommendations contained herein, whichever are more restrictive. The following recommendations have *not* been reviewed or approved by the County at this time. These recommendations may change based on obtaining approval from the County. Design of the proposed project should be made following approval from the County.

#### 5.2 Site Preparation

The area of the future single-family residence should be prepared so that foundations are founded entirely within newly placed compacted fill. General guidelines are presented below to provide a basis for quality control during site grading. It is recommended that all compacted fills be placed and compacted with engineering control under continuous observation and testing by the Geotechnical Engineer and/or his field representative, and in accordance with the following requirements.

#### 5.2.1 Removals

- a. When demolishing any existing improvements in the vicinity of the future structure and other improvements, the contractor should locate all existing foundations, floor slabs, debris pits, uncertified fill, and subsurface trash which may be present. This would include all of the materials placed to backfill the excavations made during the abandonment of the previously existing well onsite. These soils and structures should be completely removed. The resulting excavations should be cleaned of all loose soils and organic material, the exposed native soils should be scarified to a depth of 8 inches and compacted, and the excavation backfilled with compacted fill. Minimum over-excavation depths are required within the areas of the future structure and other improvements, as discussed below.
- b. Remove all vegetation and loose soil *prior* to fill placement. The general depth of stripping should be sufficiently deep to remove any root systems or organic topsoil which may be present. A careful search shall be made for subsurface trash, abandoned masonry, abandoned tanks and septic systems, and other debris during grading. All such materials, which are *not* acceptable fill material, shall be removed *prior* to fill placement. The removal of any trees or large shrubs should include complete removal of their root structures.
- c. The future building area should be over-excavated to a minimum depth of approximately 3 feet below the existing site grade, or a minimum of approximately 1 foot below the bottom of the proposed foundations, whichever is deeper. The limits of over-excavation should extend a minimum of approximately 1 to 2 feet beyond the outside perimeter of foundations, where possible. The excavated onsite earth materials may then be replaced as compacted fill, as described below.
- d. The removal and recompaction of all existing uncertified fill should include the uncertified fill associated with the abandonment of the previously existing water well onsite.
- e. In areas to receive new exterior hardscape or other miscellaneous improvements, all existing fill materials and any other loose or disturbed soil should be removed and recompacted. The depth of over-excavation in these areas should be a minimum of either 12 inches below existing grade, or 12 inches below the bottom of any improvements, or supporting aggregate base section, whichever is deeper.
- f. A careful search shall be made for any deeper areas of existing fill or loose soil during grading operations. If encountered, these loose areas should be properly removed to the firm



- underlying native soil and properly backfilled and compacted as directed by a field representative of the Project Geotechnical Engineer.
- g. The exposed bottom of removal areas should be scarified, mixed, and moisture conditioned to a minimum depth of 8 inches. This thickness of scarification is included in the thickness of removal and recompaction mentioned above, unless the bottom is unstable and requires stabilization. The scarified soil shall be moisture conditioned to near optimum moisture content and compacted to a minimum of 90% of the laboratory maximum dry density as determined by ASTM D1557. Additional lifts should *not* be placed until the present lift has been tested and shown to meet the compaction requirements.

#### 5.2.2 Bottom Stabilization

a. Depending on the time of year and recent precipitation, or should the bottom of over-excavation become flooded by rain during grading, or be found to be wet or 'pumping' due to influence from the groundwater below, additional stabilization of the bottom of over-excavation may be required. If the bottom is unstable, the use of track-mounted equipment and/or excavators should be considered to reduce the potential for disturbing the soils in the excavations near the groundwater level. If the bottom is extremely wet and pumping, the use of stabilization gravel and/or geogrid such as Mirafi 600X, may be required.

#### 5,2.3 Suitable Fill Material

- a. The excavated site soils, cleaned of deleterious material, can be re-used for fill. Rock larger than 6 inches should *not* be buried or placed in compacted fill. Rock fragments less than 6 inches may be used provided the fragments are *not* placed in concentrated pockets, and a sufficient percentage of finer grained material surrounds and infiltrates the rock voids. Furthermore, the placement of any rock must be under the continuous observation of the Geotechnical Engineer, and/or his field representative.
- b. Imported material should generally have engineering properties similar to, or more favorable than those on the subject site. Imported material will require testing to verify the engineering properties, and must be approved by the Geotechnical Engineer *prior* to placement on the site.

#### 5,2.4 Placement of Compacted Fill

- a. All fill materials should be placed in controlled, horizontal layers *not* exceeding 6 to 8 inches thick, and moisture conditioned to near optimum moisture content. Fill materials should be compacted to a minimum 90% of the laboratory maximum dry density, as determined by ASTM D1557. If either the moisture content or relative compaction does *not* meet these criteria, the Contractor should rework the fill until it does meet the criteria. If the fill materials pump (flex) under the weight of construction equipment, difficulties in obtaining the required minimum compaction may be experienced. Therefore, if soil pumping occurs, it may be necessary to control the moisture content to a closer tolerance (e.g., 2 to 3% above optimum) or use construction equipment that is not as prone to cause pumping.
- b. The field test methods to be used to determine the in-place dry density of the compacted fill shall be in conformance with either ASTM D1556 (sand cone test method) or ASTM D2922 (nuclear gauge method).
- c. Subgrade for the support of exterior concrete flatwork such as the proposed driveway and walkways shall be moisture conditioned, as required, to near optimum moisture content, and recompacted to at least 90% of the maximum dry density to a depth of at least 12 inches. For



the proposed driveway area, the same procedures should be followed, but a minimum of 95% compaction should be obtained.

# 5.2.5 Testing of Compacted Fill

a. At least one compaction test should be performed for every 500 yd<sup>3</sup> of the fill material. In addition, at least one test shall be performed for every 2 feet of fill thickness.

# 5.2.6 Inclement Weather and Construction Delays


- a. If construction delays or the weather result in the surface of the fill drying, the surface should be scarified and moisture conditioned before the next layer of fill is added. Each new layer of fill should be placed on a rough surface so planes of weakness are not created in the fill.
- b. During periods of wet weather and before stopping work, all loose material shall be spread and compacted, surfaces shall be sloped to drain to areas where water can be removed, and erosion protection or drainage provisions shall be made in accordance with the plans provided by the Civil Engineer. After the rainy period, the Geotechnical Engineer and/or his field representative shall *review* the site for authorization to resume grading and to provide any specific recommendations that may be required. As a minimum, however, surface materials previously compacted before the wet weather shall be scarified, brought to the proper moisture content, and recompacted *prior* to placing additional fill.
- c. During foundation construction, including any concrete flatwork, construction sequences should be scheduled to reduce the time interval between subgrade preparation and concrete placement to avoid drying and cracking of the subgrade, or the surface should be covered or periodically wetted to prevent drying and cracking.

#### 5.2.7 Responsibilities

- a. Representative samples of material to be used as compacted fill should be analyzed in the laboratory by the Geotechnical Engineer to determine the physical properties of the materials. If any materials other than those previously tested are encountered during grading, the appropriate analysis of this material shall be conducted by the Geotechnical Engineer as soon as practicable. Any imported soil from off-site sources shall be approved *prior* to placement.
- b. All grading work shall be observed and tested by the Project Geotechnical Engineer or their field representative to confirm proper site preparation, excavation, scarification, compaction of on-site soil, selection of satisfactory fill materials, and placement and compaction of fill. All removal areas and footing excavations shall be observed by the field representative of the Project Geotechnical Engineer before any fill or steel is placed.
- c. The lateral limits and the depths of the required over-excavation should be shown by the Civil Engineer on the grading plans.
- d. The grading contractor has the ultimate responsibility to achieve uniform compaction in accordance with the geotechnical report and grading specifications.

#### 5.3 Utility Trench Backfill

The on-site soils are suitable for backfill of utility trenches from 1-foot above the top of the pipe to the surface, provided the material is free of organic matter and deleterious substances. The natural soils should provide a firm foundation for site utilities, but any soft or unstable material encountered at pipe invert should be removed and replaced with an adequate bedding material.



The site Civil Engineer in accordance with manufacturer's requirements should specify the type of bedding materials. Granular soils may need to be imported for bedding or shading of utilities. Jetting of bedding materials should *not* be permitted unless appropriate drainage is provided and the bedding has a sand equivalent greater than 50.

Trench backfill should be placed in 8-inch lifts, moisture conditioned to near optimum moisture content, and compacted to at least 90% of the maximum density as determined by ASTM D1557, with the exception of the 1 foot below subgrade in the proposed driveway area, which should be compacted to 95% of the maximum dry density.

In areas where utility trenches pass through an existing pavement section, the trench width at the surface shall be enlarged a minimum of 6 inches on each side to provide bearing on undisturbed material for the new base and paving section to match the existing section.

Major underground utilities shall *not* cross beneath buildings unless specifically approved by the Project Civil Engineer and respective utility company. If approved, trenches crossing building areas shall be backfilled with a select gravelly sand compacted to 95% relative compaction and near optimum moisture content.

# 5.4 Temporary Excavations

Temporary excavations made as part of the required removal and recompaction operations may be made to a maximum vertical height of 3 feet. Excavations should *not* be allowed to become soaked with water or to dry out. Surcharge loads should *not* be permitted within a horizontal distance equal to the height of the excavation from the top of the excavation, unless the excavation is properly shored. Excavations that might extend below an imaginary plane inclined at 45 degrees below the edge of an existing foundation should be properly shored to maintain foundation support of the existing structure.

#### 5.5 Foundation Design

Due to the presence of potentially liquefiable soils, and the potential for surface manifestation of liquefaction including sand boils and ground fissuring, and potential total and differential liquefaction-induced settlements of up to an estimated 2.35 and 1.57 inches, respectively, a mat foundation is recommended for support of the future structure. It is recommended that the proposed foundation be supported entirely on newly placed compacted fill.

It is recommended that the perimeter of the proposed mat foundation be embedded a minimum of 18 inches in depth below the lowest adjacent grade, and 18 inches into the newly placed compacted fill. Where located adjacent to utility trenches, foundations shall extend below a 1:1 plane projected upward from the inside bottom of the trench.

# 5.5.1 Allowable Bearing Pressure and Lateral Resistance

The proposed mat foundation may be designed using a modulus of subgrade reaction of 200 kcf (kips per cubic foot). The allowable vertical and lateral bearing values given below may also be utilized in the design of the mat foundation. The bearing capacity can be increased by ½ when considering short duration wind or seismic loads.

Support Material	Allowable Bearing Pressure, psf	Allowable Sliding Friction Coefficient	Allowable Passive Resistance, psf per foot of depth	Maximum Passive Resistance, psf
COMPACTED FILL	1500	0.3	225	2250

Resistance to lateral loads can be assumed to be provided by friction along the base of the foundation, and by passive earth pressure against the side of foundation. The allowable friction coefficient may be used with the vertical dead loads, and the allowable lateral passive pressure can be utilized for the side of the foundation poured against newly placed compacted fill. These allowable values can be increased by a factor of 1.5 to convert from allowable to ultimate values. Where the soil on the resistance side of the passive wedge in not covered by a hard



surface (e.g., concrete or pavement), however, the upper 1-foot of soil shall be neglected when computing resistance due to the potential for the material to become disturbed or degraded during the life of the structure.

#### 5.5.2 Foundation Settlement

Static settlement of proposed foundation due to dead and frequently applied live loads is not expected to exceed approximately ½ to ¾ inch under the assumed loading conditions, and is expected to occur primarily upon initial application of loading. Static differential settlement is not expected to exceed approximately ¼ to ½ inch.

As described previously in this report, the maximum potential settlement due to liquefaction is anticipated to be up to approximately 2.35 inches, with potential differential settlement of up to approximately 1.57 inches over a span of 30 feet.

# 5.5.3 Steel Reinforcement

Steel reinforcing for the proposed mat foundation should be designed by the project structural engineer.

#### 5.5.4 Required Observations

*Prior* to placing concrete in the foundation excavations, an observation should be made by a field representative of the Geotechnical Engineer to confirm that the excavations are free of loose and disturbed soils, and are embedded in the recommended earth materials.

# 5.5.5 Vapor Barrier

It is recommended that a minimum 10-mil plastic vapor barrier be used under the mat foundation slab in moisture sensitive areas. The vapor barrier should be installed in accordance with the recommendations contained in the latest version of ASTM E1643. In accordance with the latest standard of practice, it is recommended that the concrete mat foundation slab be poured directly on top of the vapor barrier. No sand should be placed atop the vapor barrier. Seams of the vapor barrier should be overlapped and sealed. Where pipes extend through the vapor barrier, the barrier should be sealed to the pipes. Tears or punctures in the vapor barrier should be completely repaired *prior* to placement of concrete. The concrete mix should be designed so as to minimize possible curling of the slab. The concrete slab should be allowed to cure properly before placing vinyl or other moisture-sensitive floor covering.

# 5.6 Concrete Pavement and Patio Design

All areas to be paved or covered with concrete flatwork (driveway, patios, walkways, etc.) or other hardscape should be graded in accordance with the recommendations provided in the *Site Preparation* section of this report.

All exterior concrete pavement, patios, walkways, etc., should be a minimum of 5 inches thick, and should be reinforced with a minimum of #4 steel bars on 18-inch centers each way. Concrete subject to vehicular traffic should be underlain by a minimum of 4 inches of aggregate base.

Cracking of concrete pavement, flatwork and other hardscape can occur and is relatively common. Steel reinforcement and crack control joints are intended to reduce the risk of concrete slab cracking, as are the use of fiber reinforced concrete and proper concrete curing. Cracking can never be completely eliminated, but can be controlled through the use of proper jointing and curing.

#### 6. OBSERVATIONS AND TESTING

Prior to the start of site preparation and/or construction, we recommend that a meeting be held with the Contractor to discuss the project. We recommend that AGS be retained to perform the following tasks prior to and/or during construction. Please advise AGS a minimum 24 hours prior to any required site visit. All approved plans, permits, and geotechnical reports must be at the jobsite and be made available during inspections.



- a. Review grading, foundation, and drainage plans to verify that the recommendations contained in this report have been properly interpreted and are incorporated into the project specifications. If we are not accorded the opportunity to review these documents, we can take no responsibility for misinterpretation of our conclusions and recommendations.
- b. Observe and advise during all grading activities, including site preparation, foundation and retaining wall excavation, and placement of fill, to *confirm* that suitable fill soils are placed upon competent material and to allow design changes if subsurface conditions differ from those anticipated *prior* to the start of construction.
- c. Observe the installation of all drainage devices.
- d. *Test* all fill placed for engineering purposes to *confirm* that suitable fill materials are used and properly compacted.

#### 7. LIMITS AND LIABILITY

All building sites are subject to elements of risk that cannot be wholly identified and/or entirely eliminated. Building sites are subject to many detrimental geotechnical hazards, including but not limited to the effects of water infiltration, erosion, concentrated drainage, total settlement, differential settlement, expansive soil movement, seismic shaking, fault rupture, landsliding, and slope creep. The risks from these hazards can be reduced by employing subsurface exploration, laboratory testing, analyses, and experienced geotechnical Many geotechnical hazards, however, are highly dependent on the property owner properly maintaining the site, drainage facilities, and slope and by correcting any deficiencies found during occupancy of the property in a timely manner. Even with a thorough subsurface exploration and testing program, significant variability between test locations and between sample intervals may exist. Ultimately, geotechnical recommendations are based on the experience and judgment of the geotechnical professionals in evaluating the available data from site observations, subsurface exploration, and laboratory tests. Latent defects can be concealed by earth materials, deposition, geologic history, and existing improvements. If such defects are present, they are beyond the evaluation of the geotechnical professionals. No warranty, expressed or implied, is made or intended in connection with this report, by furnishing of this report, or by any other oral or written statement. Owners and developers are responsible for retaining appropriate design professionals and qualified contractors in developing their property and for properly maintaining the property. Retaining the services of a geotechnical consultant should not be construed to relieve the Owner, Developer, or Contractors of their responsibilities or liabilities.

The analysis and recommendations submitted in this report are based in part on our subsurface exploration, laboratory testing, site observations, and provided data on geology and the proposed site development. Our descriptions and the boring logs may show distinctions between fill and native soils, between native (e.g., alluvium, colluvium, slopewash) and bedrock formation, and between soil type (e.g., sands and silty sands). Such distinctions were based on geologic information, grading plans when available, intermittent recovered soil/bedrock samples, and judgment. Delineations between these categories of materials may not be perfect and may be subject to change as more information becomes available. For example, judgments may be clouded when recovered samples are intermittent and small in comparison to the volume of soil under study, and macrostructure that would aid the identification process are not as apparent as they would be when the borehole is geologically downhole logged by entering the excavation. When the age of the fill is old, the difference between the structure of the fill and native materials may be less pronounced, or the degree of bedrock formation weathering sometimes makes it difficult to distinguish between overlying alluvium, colluvium, or slopewash and weathered bedrock formational material. In general, our recommendations are based more on the properties of the materials than on the category of the material type such as fill, alluvium, colluvium, slopewash, or bedrock formation. Furthermore, the actual stratigraphy may be more variable than shown on the logs.



Although this report may comment on or discuss construction techniques or procedures for the design engineer's guidance, this report should *not* be interpreted to prescribe or dictate construction procedures or to relieve the contractor in any way of their responsibility for the construction.

Please be aware that the contract fee for our services to prepare this report does not include additional work that may be required, such as grading observation and testing, footing observations, plan review, or responses to governmental (regulatory) plan reviews associated with you obtaining a building permit. Where additional services are requested or required, you will be billed for any equipment costs and on an hourly basis for consultation or analysis.

The Geotechnical Engineer's actual scope of work during construction is very limited and does *not* assume the day-to-day physical direction of the work, minute examination of the elements, or responsibility for the safety of the contractor's workers. Our scope of services during construction consists of taking soil tests and making visual observations, sometimes on only an intermittent basis, relating to earthwork or foundation excavations for the project. We do *not* guarantee the contractor's performance, but rather look for general conformance to the intent of the plans and geotechnical report. Any discrepancy noted by us regarding earthwork or foundations will be referred to the Owner, project Engineer, Architect, or Contractor for action.

This report is issued with the understanding that it is the responsibility of the Owner, or of their representative, to ensure that the information and recommendations contained herein are called to the attention of the Architect and Engineers for the project and incorporated into the plan and that the necessary steps are taken to see that the Contractor carry out such recommendations in the field. Advanced Geotechnical Services, Inc., (AGS) has prepared this report for the exclusive use of the Client and authorized agents, and this report should *not* be considered transferable. We do recommend, however, that the report be given to future property Owners for the sole purpose of disclosing the report findings.

Findings of this report are valid as of the date of issuance. Changes in conditions of a property may occur with the passage of time whether attributable to natural processes or works of man on this or adjacent properties. Furthermore, changes in applicable or appropriate standards occur due, for example, to legislation and broadening of knowledge. Accordingly, findings of this report may be invalidated wholly or partially by changes outside our control. Therefore, this report is subject to our review and remains valid for a maximum period of one year, unless we issue a written opinion of its continued applicability thereafter.

In the event that any changes in the nature and design (including structural loadings different from those anticipated), or other improvements are planned, the conclusions and recommendations contained in this report shall *not* be considered valid unless the changes are reviewed and conclusions of this report modified or verified in writing.

This report may be subject to review by controlling agencies, and any modifications they deem necessary should be made a part thereof, subject to our technical acceptance of such modifications. All submissions of this report should be in its entirety. Under no circumstances should this report be summarized and synthesized to be quoted out of context for any purpose.

Test findings and statements of professional opinion do *not* constitute a guarantee or warranty, and *no* warranties, either expressed or implied, are made as to the professional advice provided under the terms of this agreement. We have strived, however, to provide our services in accordance with generally accepted geotechnical engineering practices in this community at the time of this report.



# Appendix A

Field Exploration and Boring Logs



# Appendix A Field Exploration and Boring Logs

The field exploration included a site reconnaissance and subsurface exploration. During the site reconnaissance, the surface site conditions were noted, and the approximate locations of any exploration points were determined. The following descriptions of exploration methods are generic and may include methods not used on this project. Reference to the boring logs can be made to determine which methods are applicable to this project, and any differences between what is described below and actually occurred is described on the boring logs or in the main body of the report.

The test borings were advanced by either hand digging, digging with a backhoe, or drilling. In the case of drilling, a truck-mounted rotary drilling rig with a hollow-stem auger or bucket was used to advance the borings. The method actually used is noted on the boring logs. For geologic studies when the need for visual examination of the bedding and other stratigraphic features is needed along with engineering data, the larger bucket augers are used to allow a geologist to enter the excavation for visually logging the hole. When geologically logging borings and trenches, the sides are scraped prior to logging. A prefix B is used to designate a boring made with a drilling rig. When hand dug, the boring numbers have a prefix HB. When a backhoe was used, prefixes TP (test pit) or T (trench) are used. The difference between a trench and test pit being the length of the exploration; a trench being a long narrow exploration, most commonly used for fault studies. In each case, the soils were logged by technical personnel from our office and visually classified in the field in general accordance with the Unified Soil Classification system. The field descriptions have been modified as appropriate to reflect laboratory results when preparing the final boring logs.

Relatively undisturbed samples of the subsurface materials were obtained at appropriate intervals in the borings using a steel drive sampler (2.5-inches inside diameter, 3-inches outside diameter) lined with brass, one-inch-high sample rings with a diameter of 2.4 inches. This is referred to as a modified California sampler. The boring may be advanced by drilling with a hollow-stem auger or with a wet rotary operation. If below the groundwater, the hollow-stem is filled with water or drilling mud to counteract the fluid pressure of the groundwater. The sampler was usually driven into the bottom of the borehole with successive drops of a 140-pound safety hammer connected to the sampler with either A or AW rod and falling 30 inches. An automatic hammer is usually used when drilling with a CME dill rig, and a Safe-T-Driver is used when drilling with a Mobile drill rig. When above the groundwater level, a downhole Safe-T-Driver is usually used. Studies have shown that hammer efficiencies of the automatic hammer is over 90% while that of the Safe-T-Driver is about 70%, based on impact velocities. When a bucket auger is used to advance the boring, the driving weights change with depth, depending on the weight characteristics of the telescoping kelley bar, but the height of fall is usually 18 inches. Sampler driving resistance, expressed as blows per 6 inches of penetration, is presented on the boring logs at the respective sampling depths. When the borings or trenches are excavated with a backhoe, the sampler is pushed into the soil with the force of the backhoe. A hand sampler is used when the borings or trenches are advanced by hand digging or in some cases when a backhoe is used to make the excavation. This hand sampler is similar to the conventional California sampler, but lighter weight. An approximately 8-pound hammer falling about 18 inches is used to drive the hand sampler about 6 inches into the bottom of the exploration. The type of sampler used is noted on the boring logs. In some cases, the hammer weight and falling distance deviate from those given above. The actual conditions are shown on the boring logs and supersede the conditions given above.

Ring samples were retained in close-fitting, moisture tight containers for transport to our laboratory for testing. Bulk samples, which were collected from cuttings, were placed in bags and transported to our laboratory for testing.

When noted on the boring logs, standard penetration test (SPT) samples were obtained using either a 20-inch or a 32-inch long split-barrel sampler with a 2-inch outside diameter and a 1.375-inch inside diameter when liners are used (1.5-inch inside diameter without liners). Unless noted otherwise, liners are used. This sampler is driven




into the soil with successive drops of a 140-pound, safety hammer falling 30 inches. The blows are recorded for each 6 inches of penetration for a total penetration of 18 or 24 inches. The sum of the number of blows for the last 12 inches of an 18-inch penetration or the middle 12 inches of a 24-inch penetration is referred to as the N value.

Logs, which are presented on Plates at the end of this Appendix, include a description and classification of each stratum, sample locations, blow counts, groundwater conditions encountered during drilling, results from selected types of laboratory tests, and drilling information. Keys to *Soil and Bedrock Symbols and Terms* are included on Plate A-1 and Plate A-2.

Each boring or trench, unless noted otherwise, was backfilled with cuttings at the completion of the logging and sampling. The backfill, however, may settle with time, and it is the responsibility of our client to ensure that such settlement does *not* become a liability.

# Advanced Geotechnical Services





# Advanced Geotechnical Services

		Degree of V Diagnostic			
Descriptive Term Unweathered	Discoloration Extent None	Fracture Condition Closed or discolored	Surface Characteristic Unchanged	Original cs Texture Preserved	Grain Boundary Condition Tight
Slightly Weathered	Less 20% of fracture spacing on both sides of fracture	Discolored, may contain thin filling	Partial discolora	tion Preserved	Tight
Moderately Weathered	Greater than 20% of fracture spacing on both sides of fracture	Discolored, may contain thick filling, cemented rock	Partial to comple discoloration, no friable except po cemented rocks	ot porly	Partial Opening
Highly Weathered	Throughout		Friable and poss pitted	sibly Mainly Preserved	Partial Separation
Completely Weathered	Throughout		Resembles a sol	il Partly Preserved	Complete Separation
		Discontinuit	y S <b>pacing</b>		
Bedding, Folia Very Thickly (Bedded Thickly Moderately Thinly Very Thinly  Description for M	or Structural Feature: tion, or Flow Banding d, Foliated, or Banded)	More than 2 m 60 cm to 2 m 20 to 60 cm 60 to 200 mm 20 to 60 mm	More than 6 ft 2 to 6 ft 8 to 24 in. 2.5 to 8 in. 0.75to 2.5 in.	Faults, or (	on for Joints, Other Fractures tured or Jointed)
	llation, or Cleavage , Foliated, or Cleaved)	6 to 20 mm < 6 mm	0.25 to 0.75 in < 0.25 in.	Extremely Close	
	Graphic Symbols - Bedroo	·		Rock Hardness	
Breccia  A A Claystone  Conglome  Extrusive Igneous		Shale Slitstone Slate	Classification Very Weak Weak Moderately Strong Strong Very Strong	Field Test Can be dug by hand and crus Friable, can be gouged dee will crumble readily under ligh Can be peeled with a knife, under firm blows with the sha pick. Cannot be scaped or peeled Hand held specimen breaks of pick. Difficult to scratch with knife hand held specimen.	ply with a knife and at hammer blows.  Material crumbles are end of a geologic d with a knife point.  with firm blows of the
	Separation of Fracture Wall	s		Surface Roughness	-
Description Closed Very Narrow Narrow Wide Very Wide	Separation of Walls 0 0 to 0.1 0.1 to 1.0 1.0 to 5.0 > 5.0	, mm	Description Smooth Slightly Rough Medium Rough	Classification Appears smooth and is esset touch. May be slickensided. Asperities on the fracture sur can be distinctly felt. Asperites are clearly visible	faces are visible and
	Fracture Filling  Definttion of fracture filling material		Rough Very Rough	feels abrasive to the touch. Large angular asperites cardge and high-side angle ste Near vertical steps and ri- fracture surface.	in be seen. Some ps evident.
Stained Di	scoloration of rock only. No recacture filled with recognizable to			observed, the direction of the andard discontinuity surface de	



# Boring Log B-1 Sheet 1 of 2

Proje	ct 🧐	Cha	nnel Isl	ands Beach Community Services District Client No.	4844		Date D	rilled	7/23/18
Comi	nen	t	112 La	s Palmas Street, Oxnard					
Drilli	ng (	Com	pany/Di	riller Choice Drilling F	quipment _	<u>H</u>	<u> Iollow</u>	Stem 2	Auger
Drivi	ng V	Weig	ght (lbs)	140 Average Drop (in.)30	F	Iole Dia	ameter	(in.)	6
Eleva	tion	<u> </u>			hrs on		Logg	ed By	BW
				Description of Material					
Depth, ft	Sample	Blows/6"	Graphic Symbol	This log, which is part of the report prepared by Advanced Geotechnical Services, In for the named project, should be read together with that report for complete interpretation. This summary applies only at this boring location and at the time of drilling. Subsurface conditions may differ at other locations and may change at this location with the passage of time. The data presented is a simplification of actual conditions encountered.	Attitudes	Dry Unit Weight, pcf	Moisture Content, %	-#200, %	Other Tests
5	X	11 16 19		Beach Sand (Qs) Tan medium to coarse grained SAND, dry, loose at surface, becomes slighty moist and moderately dense by a depth of approximately 1 to 2 feet		101.0	3.3	•	
	M	10 14 15				103.7	1.6		E.I.= 0
10-	M	5 7 9		becomes very moist @ 7.5 ft.  The groundwater @ 9 ft.		96.4	4.5		
-	M	6 9 12		no sample recovery @ 10 ft.					
15-		6 9 15		becomes fine to coarse grained sand, wet, dense			22.5		
20	X	4 8 13					13.7		
25-	X	14 26 28					14.7		



# Boring Log B-1 Sheet 2 of 2

Proje	ct C	Cha	nnel Isl	lands Beach Community Services District Client No.		4844		Date D	rilled	7/23/18
Com	men	t _	112 La	as Palmas Street, Oxnard						
Drill	ing (	Com	pany/D	riller Choice Drilling	Equ	ipment _	Н	[ollow	Stem A	<u> Luger</u>
Drivi	ng V	Veig	ght (lbs)	Average Drop (in.)	30	Н	ole Dia	ameter	(in.)	6
Eleva	ation	ı		ft Depth to Water 9.0 ft After	h	nrs on		Logg	ed By	BW
				Description of Material						
Depth, ft	Sample	Blows/6"	Graphic Symbol	This log, which is part of the report prepared by Advanced Geotechnical Service for the named project, should be read together with that report for complete interpretation. This summary applies only at this boring location and at the time drilling. Subsurface conditions may differ at other locations and may change a location with the passage of time. The data presented is a simplification of actu conditions encountered.	es, Inc. e of t this al	Attitudes	Dry Unit Weight, pcf	Moisture Content, %	-#200, %	Other Tests
	X	6		becomes medium to coarse grained sand, wet, dense				24.7 19.3		
35-		12		silty lense at bottom of 30 ft. sample, firm, very moist				13.0		
-		6 8 15		becomes gray, medium to coarse grained, slightly silty				19.1		
40-		8 10 27		Light gray fine grained Sandy SILT, stiff, very moist, minor clay		-		22.1		
45-	X	4 5 7		grades siltier				37.6		
50-	X	7 16 19				-		24.0		
55-				Total Depth Explored = 51.5 ft. Groundwater Encountered @ 9 ft. No Groundwater Encountered						



Boring Log B-2

							Shee	et <u>I</u>	_ ofI
Proje	ct (	Chai	nnel Isl	ands Beach Community Services District Client No.	4844		Date D	rilled	7/23/18
Com	ment	t _	112 La	ns Palmas Street, Oxnard					
Drilli	ing C	Com	pany/Di	riller Choice Drilling	Equipment	<u>I</u>	<b>Hollow</b>	Stem A	Auger
Drivi	ng V	Veig	tht (lbs)	140 Average Drop (in.)	30	Hole Di	ameter	(in.)	6
Eleva	ation			ft Depth to Water 8.5 ft After	hrs on		Logg	ed By	BW
				Description of Material					
Depth, ft	Sample	Blows/6"	Graphic Symbol	This log, which is part of the report prepared by Advanced Geotechnical Services, for the named project, should be read together with that report for complete interpretation. This summary applies only at this boring location and at the time o drilling. Subsurface conditions may differ at other locations and may change at th location with the passage of time. The data presented is a simplification of actual conditions encountered.	Inc. Attitude	Dry Unit Weight, pcf	Moisture Content, %	-#200, %	Other Tests
	M	15 18 18		Beach Sand (Qs)  Tan medium to coarse grained SAND, dry, loose at surface, becomes slighty moist and moderately dense by a depth of approximately 1 to feet	02	85.1	26.5		
5-	X	9 13 15		becomes medium to coarse grained SAND, slightly moist, dense		102.8	2.5		
-	H	5 7 7		becomes very moist @ 7.5 ft.  groundwater encountered @ 8.5 ft.		94.5	20.2		
10-	X	2 2 3					24.5		
15-	X	14 16 17		becomes coarse grained sand, wet, dense			17.5		
20-				Total Depth Explored = 16.5 ft. Groundwater Encountered @ 8.5 ft. Backfilled with Spoils 7/23/2018					
-									



Appendix B

**Laboratory Testing** 



# Appendix B Laboratory Testing

A laboratory test program is designed for each project to evaluate the physical and mechanical properties of the soil and bedrock materials encountered at the site during our field exploration program. Laboratory tests were conducted on representative samples for the purpose of classification and determining their properties for use in analyses and evaluations. The most common laboratory tests include moisture-density, Atterberg limits, grain-size analyses (sieve and hydrometer analyses), sand equivalent, direct shear, consolidation, compaction, expansion index, and *R*-values. The following descriptions of test methods are generic and may include methods not used on this project. Reference to the boring logs and test results on Plates attached to this appendix will show which tests were performed for this project. Laboratory testing is performed in general accordance with the most recent ASTM (2007) test designations available at the time of testing.

#### **Classification Tests**

Classification testing is performed to identify differences in material behavior and to correlate the results with shear strength and volume change characteristics of the materials. Classification testing includes unit weight (e.g., dry density), moisture content, Atterberg limits, grain size analyses (sieve and hydrometer), and sand equivalent.

# Moisture-Density Test

Site soils were classified in the laboratory in accordance with the Unified Soil Classification System. Moisture contents are performed in general accordance with ASTM Test Designation D2216 and unit weights were determined in general accordance with ASTM Test Designation D2937. Field moisture contents and dry unit weights were determined for the ring samples obtained in the field. Field moisture contents and dry unit weights are shown on the boring logs in Appendix A.

# Sieve Analysis

Sieve analysis tests were conducted on the on-site soils in general accordance with sieve analysis test procedure from ASTM Test Designation D422. This method covers the quantitative determination of the distribution of particle sizes in soils. If this test was performed, the results are presented on Plates attached to this appendix.

#### Hydrometer Test

Hydrometer tests were performed in general accordance with ASTM Test Designation D422. If this test was performed, the results are presented on Plates attached to this appendix. Samples with obviously little course material and a high percentage of fines were prepared with a wet method (ASTM Test Designation D2217) rather than air-drying the sample and pulverizing with a mortar and pedestal.

#### **Shear Tests**

Direct shear tests were performed in general accordance with ASTM D3080 to determine the shear strength parameters of undisturbed on-site soils or remolded soil specimens. The samples are usually tested in an artificially saturated condition. This is accomplished by soaking the specimens in a confined container for a period of one or 2 days, depending on the permeability of the material. The specimen, 1-inch-high and 2.4-inch-diameter, is placed in the shear device, and a vertical stress is applied to the specimen. The specimen is allowed to reach an equilibrium state (swell or consolidate). The specimen is then sheared under a constant rate of deformation. The rate of deformation for a slow test, sufficiently slow to presumably allow drainage, is selected from computed or measured consolidation rates to simulate full drainage (full dissipation of any tendency for pore water pressure changes) during shear. A rate of displacement of 0.005 inches per minute was used for the most tests. The process usually is repeated for 3 specimens, each under different vertical stresses. The results from the 3 tests are plotted on a diagram of shear stress and normal (vertical) stress at failure, and linear approximations are drawn of the failure curves to determine the angle of internal friction and cohesion. The first moisture content



shown on the graphs (associated with peak values) is for either the in-situ condition or the remolded condition, and the second moisture content (associated with ultimate value) is for the soaked condition.

#### **Consolidation Test**

Consolidation tests were performed in general accordance with ASTM D2435 and D5333 on selected samples to evaluate the load-deformation characteristics of the earth soils. The tests were performed primarily on material that would be most susceptible to consolidation under anticipated foundation loading. The soil specimen, contained in a 2.4-inch-diameter, 1.0-inch-high sampling ring, is placed in a loading frame under a seating pressure of 0.1 ksf. Vertical loads are applied to the samples in several geometric increments, and the resulting deformations were recorded at selected time intervals. When the pressure reaches a preselected effective overburden pressure (often 2 ksf) and the specimen has consolidated under that pressure, the laboratory technician adds water to the test cell and records the vertical movement. After the specimen reaches equilibrium with the addition of water, the technician continues the loading process, usually up to a pressure of about 8 ksf. The specimen is then unloaded in increments, and the test is dismantled. The results of the test are presented in terms of percent volume change versus applied vertical stress. If this test was performed, the results are presented on Plates attached to this appendix.

#### **Compaction Test**


Compaction tests provide information on the relationship between moisture content and dry density of the soil compacted in a given manner. The maximum density is obtained for a given compaction effort at an optimum moisture content. Specifications for earthwork are in terms of the unit weight (or dry density) expressed as a percentage of the maximum density, and the moisture content compared to the optimum moisture content. Compaction tests were performed in general accordance with ASTM Test Designation D1557 to determine the maximum dry densities and optimum moisture contents of the on-site soils. If this test was performed, the results are presented on Plates attached to this appendix.

#### **Expansion Index Test**


The expansion index test provides an assessment of the potential for expansion or heave that could be detrimental to foundation or slab performance. Expansion Index tests are performed on shallow on-site soils in general accordance with expansion test procedures in ASTM D4829. In this test, a specimen is compacted at a degree of saturation between 45% and 55% in a 4.01-inch-diameter, 1.0-inch-high ring. The specimen is subjected to a seating pressure of 144 psf, water is added to the test cell, and swell is monitored until the expansion stops. The volume of swell is converted to an expansion index. Any test results are summarized on the boring logs in Appendix A.

#### Sample Remolding

In some cases, remolded samples are used when performing direct shear tests and consolidation tests. Samples are remolded to a specified moisture and density by compacting the soil in a 2.42-inch-diameter sample ring. The specified moisture content is either at optimum or a few percentage points above optimum. The specified dry density is usually at a relative compaction of 90%. The required moisture is added to and mixed with dry soil, providing a homogeneous mixture. A 2.42-inch-diameter ring is placed in a 6-inch-diameter compaction mold, and soil is placed in the mold to above the ring. The soil is then compacted with a 5.5-pound hammer with a free-fall drop of 12 inches. The sample is trimmed, and the dry density is determined. If the dry density deviates more than about one pound per cubic foot from the specified dry density, the process is repeated with the number of blows altered to better achieve the specified dry density.







Stress, ksf

Open Symbol At Field Moisture, Solid Symbol After Submersion in Water

S	Specimen Identification		ecimen Identification Classification		MC%	
0	B-1	5.0	Tan medium to coarse grained SAND	99.3	4.2	
•	B-1	5.0	*UNDISTURBED*	101.8	16.7	

Project


Channel Islands Beach Community Services
District - 112 Las Palmas Street, Oxnard

Client No. \_\_\_ Date 4844

8/7/18



**Consolidation Test** 




	O 1 0011 1		• - Oillinate Shear		<u> </u>	idual Oi	IGai
	Specimen I	dentification	Classification	DD	MC%	c, ksf	phi
0	B-1	5.0	Tan medium to coarse grained SAND	96.0	15.5	0.34	24
•	B-1	5.0	*REMOLD*	96.0	19.8	0.29	22
						-	

Project

Channel Islands Beach Community Services District - 112 Las Palmas Street, Oxnard Client No. Date 4844 8/7/18



Shear Test Diagram



O - Peak Shear

# - Ultimate Shear

 $\triangle$  - Residual Shear

			• - Oillinate Shear			<u> </u>	nauai Oi	Cui
	Specimen le	Specimen Identification Classification			DD	мс%	c, ksf	phi
0	B-2	5.0	Tan fine to coarsegrained SAND		95.7	6.9	0.16	35
•	B-2	5.0	*UNDISTURBED*		95.7	23.3	80.0	32
				_				

Project


Channel Islands Beach Community Services
District - 112 Las Palmas Street, Oxnard

Client No. Date 4844


8/7/18



Shear Test Diagram









## **LABORATORY ANALYSIS RESULTS**

Client:

Advanced Geotechnical Services, Inc.

**Project No:** 

4894

Project Name: Channel Island Beach CSD

AA Project No: A97589

Date Received: 07/24/18
Date Reported: 08/06/18

#### **ANALYTICAL DATA SUMMARY**

Analyte	Sample Name	Result	MRL Units	Dilution	Prepared	Analyzed	Method
	ġ	Chloride by Ion Cl	hromatography	Ĺ			
Chloride	B-1@5'	22	5.0 mg/kg	1	07/30/18	07/30/18	EPA 300.0
		General Chemis	stry Analyses				
pН	B-1@5'	7.5	0.50 pH Units	1	07/27/18	07/27/18	9045C
Specific Conductar	nce (EC)B-1@5'	270	umhos /cm	1	07/27/18	07/27/18	EPA 120.1
		Sulfate by Ion Ch	romatography				
Sulfate	B-1@5'	16	5.0 mg/kg	1	07/30/18	07/30/18	EPA 300.0

Meland

Allen Aminian QA/QC Manager



Appendix C

**Seismicity Study** 

# **ZUSGS** Design Maps Summary Report

## **User-Specified Input**

Report Title C.I.Beach Comm. Serv. Dist. 112 Las Palmas

Thu July 5, 2018 23:08:32 UTC

Building Code Reference Document ASCE 7-10 Standard

(which utilizes USGS hazard data available in 2008)

**Site Coordinates** 34.16466°N, 119.22851°W

Site Soil Classification Site Class D - "Stiff Soil"

Risk Category I/II/III



#### **USGS-Provided Output**

 $S_s = 2.053 g$ 


 $S_{MS} = 2.053 g$ 


 $S_{DS} = 1.369 g$ 

 $S_1 = 0.727 g$   $S_{M1} = 1.090 g$ 

 $S_{D1} = 0.727 g$ 

For information on how the SS and S1 values above have been calculated from probabilistic (risk-targeted) and deterministic ground motions in the direction of maximum horizontal response, please return to the application and select the "2009 NEHRP" building code reference document.





For PGA<sub>M</sub>, T<sub>L</sub>, C<sub>RS</sub>, and C<sub>R1</sub> values, please view the detailed report.

Although this information is a product of the U.S. Geological Survey, we provide no warranty, expressed or implied, as to the accuracy of the data contained therein. This tool is not a substitute for technical subject-matter knowledge.

# **ZUSGS** Design Maps Detailed Report

ASCE 7-10 Standard (34.16466°N, 119.22851°W)

Site Class D - "Stiff Soil", Risk Category I/II/III

#### Section 11.4.1 — Mapped Acceleration Parameters

Note: Ground motion values provided below are for the direction of maximum horizontal spectral response acceleration. They have been converted from corresponding geometric mean ground motions computed by the USGS by applying factors of 1.1 (to obtain  $S_s$ ) and 1.3 (to obtain  $S_1$ ). Maps in the 2010 ASCE-7 Standard are provided for Site Class B. Adjustments for other Site Classes are made, as needed, in Section 11.4.3.

#### From Figure 22-1 [1]

 $S_s = 2.053 g$ 

## From Figure 22-2<sup>[2]</sup>

 $S_1 = 0.727 g$ 

#### Section 11.4.2 — Site Class

The authority having jurisdiction (not the USGS), site-specific geotechnical data, and/or the default has classified the site as Site Class D, based on the site soil properties in accordance with Chapter 20.

Table 20.3-1 Site Classification

Site Class	$\overline{v}_s$	$\overline{ extsf{N}}$ or $\overline{ extsf{N}}_{ch}$	- S <sub>u</sub>
A. Hard Rock	>5,000 ft/s	N/A	N/A
B. Rock	2,500 to 5,000 ft/s	N/A	N/A
C. Very dense soil and soft rock	1,200 to 2,500 ft/s	>50	>2,000 psf
D. Stiff Soil	600 to 1,200 ft/s	15 to 50	1,000 to 2,000 psf
E. Soft clay soil	<600 ft/s	<15	<1,000 psf

Any profile with more than 10 ft of soil having the characteristics:

- Plasticity index PI > 20,
- Moisture content  $w \ge 40\%$ , and
- Undrained shear strength  $\bar{s}_{u}$  < 500 psf

See Section 20.3.1

21.1

For SI:  $1ft/s = 0.3048 \text{ m/s} 1 \text{lb/ft}^2 = 0.0479 \text{ kN/m}^2$ 

F. Soils requiring site response analysis in accordance with Section

# Section 11.4.3 — Site Coefficients and Risk–Targeted Maximum Considered Earthquake (MCE<sub>R</sub>) Spectral Response Acceleration Parameters

Table 11.4–1: Site Coefficient  $F_a$ 

Site Class	Mapped MCE <sub>R</sub> Spectral Response Acceleration Parameter at Short Period							
	S <sub>s</sub> ≤ 0.25	$S_s = 0.50$	$S_s = 0.75$	S <sub>s</sub> = 1.00	S <sub>s</sub> ≥ 1.25			
А	0.8	0.8	0.8	0.8	0.8			
В	1.0	1.0	1.0	1.0	1.0			
С	1.2	1.2	1.1	1.0	1.0			
D	1.6	1.4	1.2	1.1	1.0			
E	2.5	1.7	1.2	0.9	0.9			
F		See Se	ection 11.4.7 of	ASCE 7				

Note: Use straight-line interpolation for intermediate values of S<sub>s</sub>

For Site Class = D and  $S_s = 2.053 g$ ,  $F_a = 1.000$ 

Table 11.4–2: Site Coefficient  $F_v$ 

Site Class	Mapped MCI	Mapped MCE <sub>R</sub> Spectral Response Acceleration Parameter at 1–s Period								
•	S₁ ≤ 0.10	$S_1 = 0.20$	$S_1 = 0.30$	$S_1 = 0.40$	$S_1 \ge 0.50$					
Α	0.8	0.8	0.8	0.8	0.8					
В	1.0	1.0	1.0 1.0	1.0	1.0					
С	1.7	1.6	1.5	1.4	1.3					
D	2.4	2.0	1.8	1.6	1.5					
E	3.5	3.2	2.8	2.4	2.4					
F		See Se	ection 11.4.7 of	ASCE 7						

Note: Use straight-line interpolation for intermediate values of  $\boldsymbol{S}_{1}$ 

**Equation (11.4-1):** 

$$S_{MS} = F_a S_S = 1.000 \times 2.053 = 2.053 g$$

**Equation (11.4-2):** 

$$S_{M1} = F_v S_1 = 1.500 \times 0.727 = 1.090 g$$

Section 11.4.4 — Design Spectral Acceleration Parameters

Equation (11.4-3):

$$S_{DS} = \frac{2}{3} S_{MS} = \frac{2}{3} \times 2.053 = 1.369 g$$

Equation (11.4-4):


$$S_{D1} = \frac{1}{3} S_{M1} = \frac{1}{3} \times 1.090 = 0.727 g$$

Section 11.4.5 — Design Response Spectrum

From Figure 22-12 [3]

 $T_L = 8$  seconds






Spectral Response Acceleration, Sa (g)

# Section 11.4.6 — Risk-Targeted Maximum Considered Earthquake ( $MCE_R$ ) Response Spectrum

Spectral Response Acceleration, Sa (g)

The  $MCE_R$  Response Spectrum is determined by multiplying the design response spectrum above by 1.5.



Section 11.8.3 — Additional Geotechnical Investigation Report Requirements for Seismic Design Categories D through F

From Figure 22-7<sup>[4]</sup>

PGA = 0.768

**Equation (11.8-1):** 

$$PGA_{M} = F_{PGA}PGA = 1.000 \times 0.768 = 0.768 g$$

Table 11.8–1: Site Coefficient  $F_{PGA}$ 

Site	Manno	MCE Coomotri	c Mean Peak Gr	ound Accolorati	on DCA
Class	PGA ≤ 0.10	PGA = 0.20	PGA = 0.30	PGA = 0.40	PGA ≥ 0.50
А	0.8	0.8	0.8	0.8	0.8
В	1.0	1.0	1.0	1.0	1.0
С	1.2	1.2	1.1	1.0	1.0
D	1.6	1.4	1.2	1.1	1.0
Е	2.5	1.7	1.2	0.9	0.9
F		See Se	ction 11.4.7 of	ASCE 7	

Note: Use straight-line interpolation for intermediate values of PGA

For Site Class = D and PGA = 0.768 g,  $F_{PGA} = 1.000$ 

Section 21.2.1.1 — Method 1 (from Chapter 21 – Site-Specific Ground Motion Procedures for Seismic Design)

From <u>Figure 22-17</u> [5]

 $C_{RS} = 0.926$ 

From <u>Figure 22-18</u> [6]

 $C_{R1} = 0.936$ 

## Section 11.6 — Seismic Design Category

Table 11.6-1 Seismic Design Category Based on Short Period Response Acceleration Parameter

VALUE OF S <sub>ps</sub>	RISK CATEGORY							
VALUE OF 3 <sub>DS</sub>	I or II	III	IV					
S <sub>DS</sub> < 0.167g	А	А	А					
$0.167g \le S_{DS} < 0.33g$	В	В	С					
$0.33g \le S_{DS} < 0.50g$	С	С	D					
0.50g ≤ S <sub>DS</sub>	D	D	D					

For Risk Category = I and  $S_{ps}$  = 1.369 g, Seismic Design Category = D

Table 11.6-2 Seismic Design Category Based on 1-S Period Response Acceleration Parameter

VALUE OF S <sub>D1</sub>	RISK CATEGORY								
VALUE OF S <sub>D1</sub>	I or II	III	IV						
S <sub>D1</sub> < 0.067g	A	A	А						
$0.067g \le S_{D1} < 0.133g$	В	В	С						
$0.133g \le S_{D1} < 0.20g$	С	С	D						
0.20g ≤ S <sub>D1</sub>	D	D	D						

For Risk Category = I and  $S_{D1} = 0.727$  g, Seismic Design Category = D

Note: When  $S_1$  is greater than or equal to 0.75g, the Seismic Design Category is **E** for buildings in Risk Categories I, II, and III, and **F** for those in Risk Category IV, irrespective of the above.

Seismic Design Category  $\equiv$  "the more severe design category in accordance with Table 11.6-1 or 11.6-2" = D

Note: See Section 11.6 for alternative approaches to calculating Seismic Design Category.

#### References

- 1. *Figure 22-1*: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-1.pdf
- 2. *Figure 22-2*: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-2.pdf
- 3. *Figure 22-12*: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-12.pdf
- 4. Figure 22-7: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-7.pdf

- 5. Figure 22-17: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-17.pdf
- 6. Figure 22-18: https://earthquake.usgs.gov/hazards/designmaps/downloads/pdfs/2010\_ASCE-7\_Figure\_22-18.pdf



## Appendix D

**Liquefaction Evaluation** 

#### Input Data in Shaded Areas

Client Number 4844 Client Name C.I. Beach Community Services Dist.  Date Drilled 7/23/18 Boring B-1	



a<sub>max</sub>/g Magnitude Groundwater Depth (ft) Reference Pressure, p<sub>a (fid)</sub> Reference Pressure, pa (dry)

0.768	
6.90	
<b>35.0</b> ≥ 5.0	
2.1164	
1.0582	

(Historic High)

N Adjustments - Liners (SPT Samples) N Adjustments - Hole Diameter N Adjustments - Energy

1.20 1.00 1.33 10.08

Field Groundwater Depth (ft) Method (S = SPT) Unit Weight of Water (kcf)

(Current) S 0.0624

NL = Not Susceptible to Liquefaction

#### **B1 Liquefaction Evaluation**

Depth, Feet	Total Unit Weight, Yt	Overburden Pressure, σ <sub>v</sub>	Overburden Pressure, σ <sub>v</sub> '	Field Effective Overburden Pressure, $\sigma_{v}$	C <sub>N</sub>	r <sub>d</sub>	CSR <sub>M=7.5</sub>	Soil Type*	% Fines	N	(N <sub>1</sub> ) <sub>60</sub>	Adjusted for Fines Content (N <sub>1</sub> ) <sub>60</sub>	Rod Length Adjust	Ks	CRR <sub>M=7.5</sub>	Safety Factor, SPT Method	Volumetric Strain	Layer Settlement, (inches)	Cumulative Liquefaction Settlement, (inches)
0.0	لـــــا	0.00	0.00	0.00	<u> </u>														
1.5	0.125	0.19	0.19	0.19	1.70	1.00	0.403		And the Park of the Park	50.0	101.7	101.7	0.75	1.00	5.000	Above GWT	0.000	0.000	0.000
3.0	200 doc	0.38	0.38	0.38	1 4 70 1	0.00	0 400 I		THE AREA TO THE PERSON NAMED IN	Langue Cara Land Address Communication	00.0	20.0							
4.0 5.0	0:125	0.50 0.63	0.50 0.63	0.50	1.70	0.99	0.400		2000年	19.4	39.6	39.6	0.75	1.00	5.000	Above GWT	0.000	0.000	0.000
6.3		0.63	0.63	0.63	1.65 <b>l</b>	0.99	0.442 <b>I</b>		1000	Latte to understand of	24.7	31.7	0.75	1 400 1	0.207	1 50 1	0.000	1 0000	0.000
7.5	20.123.X	0.78	0.70	0.78	1.00	0.99	0.442		S = 50 8/2	16:17	31.7	31.1	0.75	1.00	0.387	NL_	0.000	0.000	0.000
8.8	0.125	1.09	0.76	1.09	1.39 <b>I</b>	0.98	0.504 <b>I</b>		are a second	l 8.9 l	16.8	16.8	0.85	1.00	0.182	I 0.36 I	0.018	0.549	0.549
10.0		1.25	0.94	1.19	1.55	0.30	0.504		PROFESSION OF STREET	#####O.30####	10.0	10.0	0.00	1.00	0.102	0.50	0.010	0.549	0.549
12.5	0.125	1.56	1.09	1.34	1.25	0.97	0.543 I		Alexandra de Caracter	11.7	19.9	19.9	0.85	1.00	0.216	I 0.40 I	0.016	0.972	1.521
15.0		1.88	1.25	1.50		0.01	0.0.0		The second secon	**************************************		10.0	0.00	1.00	0.210	0.10	0.010	0.572	1.021
16.3	0.125	2.03	1.33	1.58	1.16	0.97	0.571		3.3	24.0	42.1	42.1	0.95	I 1.00 (	5.000	l NL	0.000	0.000	1.521
17.5	1	2.19	1.41	1.66	i											•			
18.8	0:125	2.34	1.49	1.74	1.10	0.96	0.582		3.3	24.0	40.2	40.2	0.95	1.00	5.000	NL_	0.000	0.000	1.521
20.0		2.50	1.56	1.81													_	_	
21.3	0.125	2.66	1.64	1.89	1.06	0.95	0.589		6.5	21.0	33.7	34.0	0.95	1.00	0.502	NL NL	0.000	0.000	1.521
∞ 22.5 ⇔		2.81	1.72	1.97	L														
23.8	0.125	2.97	1.80	2.05	1.02 l	0.95	0.593		6.5	21:0 J	32.4	32.6	0.95	1.00	0.435	NL !	0.000	0.000	1.521
25.0	E-Posto con	3.13	1.88 1.96	2.13 2.20		0.04	0.500 1		* Storocola cancellation	introde 4:0 9537 :	84.4	86.2	1 4 00	1 400 1	5.000	1 50 1	0.000	0.000	1.521
26.3 27.5	0.125	3.28	1.96	2.20	0.98	0.94	0.596			[22%54:U2%*]	84.4	86.2	1.00	1.00	5.000	l NL I	0.000	0.000	1.521
1 28.8	0.125	3.59	2.03	2.26	I 0.95 I	0.93	0.596		8.6	1 54.0 l	81.6	83.3	1.00	I 1.00 I	5.000	I NL	0.000	0.000	1.521
30.0	**U.123**	3.75	2.19	2.44	0.50	0.55	0.550		arms to 0.0 minus	7-2-04:U4-7-1	01.0	00.0	1.00	1.00	3.000	INL .	0.000	0.000	1.021
31.3	0:125	3.91	2.27	2.52	0.92 <b>i</b>	0.91	0.595		598	18.0 4	26.3	I 36.6	1.00	1.00 [	5.000	I NL	0.000	0.000	1.521
32.5	1	4.06	2.35	2.60	l 0.02 1	0.01	0.000		[31.04.00.0V.mac.	1300 (10) <b>210</b> (4.74)	20.0	, 55.5		1.00	0.000		0.000	0.000	
33.8	0.125	4.22	2.42	2.67	0.89	0.90	0.593		· 59.8 ···	18.0	25.6	35.7	1.00	0:99	5.000	[ NL I	0.000	0.000	1.521
- 35.0		4.38	2.50	2.75															-
36.3	0.125	4.53	2.58	2.83	0.86	0.88	0.591		11.6	23.0	31.7	34.1	1.00	0.98	0.499	NL I	0.000	0.000	1.521
37.5		4.69	2.66	2.91															
38.8	0.125	4.84	2.74	2.99	0.84	0.86	0.587		[11.6	23.0	30.9	33.2	1.00	0.97	0.451	NL _	0.000	0.000	1.521
40.0	1	5.00	2.82	3.07	l				I have been a Carbon of						5,000		0.000	1 0000	-
41.3	0.125	5.16	2.89	3.14	0.82	0.84	0.583		59.1	§ 37.0	48.5	<u> </u> 63.1	1.00	0.96	5.000	NL	0.000	0.000	1.521
42.5	1	5.31	2.97	3.22	1 000	0.00	0.570		l distinguismen	- Billion non-common	172	1 647	1.00	I 0.96 I	5.000	I NL	0.000	0.000	1.521
43.8 45.0	0.125	5.47	3.05	3.30	0.80	0.82	0.578		59:1	37.0	47.3	61.7	1.00	L 0.90	5.000	J NL	0.000	0.000	1.521
46.3	0.125	5.63 5.78	3.13	3.38	1 <u> </u>	0.79	0.573		54.1	12.0	15.0	23.0	1.00	0.95	0.242	0.42	0.014	0.410	1.931
40.3	≝.,U.125 ;;	5.76	3.29	3.54	0.76	0.79	0.3/3		Passe 34:19973	I Z.U	13.0	23.0	1.00	0.55	0.242	t 0.42	0.014	0.410	1.331
48.8	I 0.125	6.09	3.36	3.61	0.77	0.77	0.568		541	12.0	14.7	22.6	1.00	0.94	0.235	0.41	0.014	0.418	2.349
I 50.0		6.25	i 3.44	3.69	, <u>5.77  </u>	0.77	1 0.000		IN PUC TALDER	a programa <b>⊆, U</b> gravita		. 22.0	1 1.00	1 0.0T I	5.200		5.511	. 5.110	2.5 10
1		0.20	, <del>0.11</del>	2.00														total -	2 35

total = 2.35

<sup>\*</sup> C indicates clay or other non-liquefiable, fine grained soils (based on hydrometer and/or Atterberg testing), otherwise assumed to be potentially liquefiable.



#### Appendix E References

The following list includes the citations of references referred to in this report.

American Society for Testing and Materials (2013), **ASTM Standards**, Section 4: Construction, Volume 04.08 Soil and Rock (I): D 420 – D 5611, West Conshohocken, PA.

Bartlett, S. F. and Youd, T. L. (2002), *Revised Multilinear Regression Equations for Prediction of Lateral Spread Displacement*, **Journal of Geotechnical and Geoenvironmental Engineering**, Vol. 128, No. 12, ASCE, ISSN 1090-0241/2002/12-1007-1017, December 1, 2002.

California Geological Survey (2008), Guidelines for Evaluating and Mitigating Seismic Hazards in California, Special Publication 117A, Division of Mines and Geology.

California Geological Survey (2002), Seismic Hazard Zone Report for the Oxnard 7.5-Minute Quadrangle, Ventura County, California, Seismic Hazard Zone Report 052.

California Geological Survey (2002), State of California Seismic Hazard Zones Map, Oxnard Quadrangle, Released: December 20, 2002.

Department of the NAVY, NAVFAC Design Manual 7.02, (1986), Foundations and Earth Structures, Naval Facilities Engineering Command, September.

Google (2018), Google Earth Interactive web program http://www.google.com/earth

International Conference of Building Officials and California Building Standards Commission (2016), 2016 California Building Code.

Robertson, P. K. and Wride, C. E. (1997), Cyclic Liquefaction and Its Evaluation based on the SPT and CPT, Proceedings of the NCEER Workshop on Evaluation of Liquefaction Resistance of Soils, National Center for Earthquake Engineering Research, Technical Report NCEER-97-0022, pp. 41 – 87.

Southern California Earthquake Center (1999), Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Liquefaction Hazards in California, Martin, G. R. and Lew, M. Co-Chairs and Editors, University of Southern California, March 1999.

Tokimatsu, K. and Seed, H. B. (1987), *Evaluation of Settlements in Sands Due to Earthquake Shaking*, **Journal Geotechnical Engineering**, ASCE, Vol. 113, No. 8, pp. 861-878.

United States Geological Survey, (2014), **Seismic Design Maps** web program, last modified March 10, 2014 http://earthquake.usgs.gov/designmaps/us/application.php

Youd, T. L. and Idriss, I. M. (1997), *Summary Report*, **Proceedings of the NCEER Workshop on Evaluation of Liquefaction Resistance of Soils**, National Center for Earthquake Engineering Research, Technical Report NCEER-97-0022, pp. 1 – 40.

Youd et al (2001), Liquefaction Resistance of Soils: Summary Report from the 1996 and 1998 NCEER/NSF Workshop on Evaluation of Liquefaction Resistance of Soils, **Journal Geotechnical Engineering**, ASCE, Vol. 127, No. 10, pp. 817-833.



## Appendix F

**Well Abandonment Documents** 



VA. NE-COCCOA (New 12/18)

#### County of Ventura

# WELL PERMIT APPLICATION 600 South Victoria Avenue, Ventura CA 93009

	<b>6</b>		toria Avenue, Ventu	74 CA 93	009 Perm	iit No53	331	
The second	annel I slands	13-44	en <b>kl</b> au <b>sk</b> a kadhens (87 <b>ne</b> e		**************************************	t to the survey of the survey of the state of the survey o	MANAGEMENT OF THE PROPERTY OF THE PARTY OF T	MAJA PEN
Co	TREPHONE HUNGER	4.44 35	3 Sout Man	Ma De	OXNar	2 CA	. **	
DW16	TELEPHONE MANAGER	1444	E OF WALL DRILLER	HOMERIOGPIYIYYALUM	A LANGE	(ZCR)	WE HAVE	economica:#
180	51985-602L		Kes Permp & 1	Ori))/-	18 IN.	10	70-98	3
1 har	eby agree to comply with a	all regulations penalping	to well construction.	repair, mos	Mication and c	estruction.	Within 30 day	's of
Reso	alerion of work, I will furnished by the Division with a comp	in the Ventura County Pt	utilic Works Agency, ' the well. Any modific	yvater Reso	urçes ano asp is permit (equ	ires approva	epartment, W. I by the Direc	ater cor.
C>!!	(805) 654-2907 or 654-2004	. When signed by the D	irector of Public Wor	ks, Uris op	ationtion is a p	oomit.		
1000	mer's Biggranters		Bate	•	***************************************			
Carlotte	ated Dates of Work. Start.		Completion	. 1-27	-21	(05)	485-3012 985-308/	<u> 5</u>
*******************************	erotymuseum alkada alkada karanta kara		ners feels de marie de 1840 en region propins	and the second s	productive and accommendation	NOT THE RESIDENCE OF THE PARTY	THE RESERVE AND ASSESSED FOR PARTY OF THE PROPERTY OF THE PARTY OF THE	OR STATE OF THE ST
8	PE OF WORK /Check/	USE (Check) ublic Domestic E	EQUIPMENT /	Cheek/	WELL DEPTH	Steel	DSED CASINO	3.   <b>12</b>
		ancultural Comesic C			250	PVC		ō
		UFT Invest/Clean-up			DIAMETER WELL BORE	Other	· • • • • • • • • • • • • • • • • • • •	. Ö
	koving (No) 🔲 SI	te Assess/Leak Detect C		<b>5</b> 3-	1:2"	Diameter	1, 2''.	
Borel	nole (No) 🔲 O	)therC	Other		NCHES	Wall or G	388 88¢	ekinasa.ank
	T PROPOSED SEALI	NG ZONE(s)	SEALING MA		.034		INS OR SCHE	EN
From		with Neat Cement		Bentonite	F		mm ~ 4. **********************************	Ft
	to	with	Cement Grout []	Concrete		· • • • • • • • • • • • • • • • • • • •	10	i-t
	, 10	Patrician and Company of the Company	·/-	ericking	a. (4)(V)		Ant 107	******
Perm	it Start Date 01/28/03	<u>s 610.00</u>	FOR OFFICE USE Fee Paid On	01/14/	03	color No	<u>5295</u>	
Į							1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	<del>unionemid</del> e.
î	ation Date07/28/03		2/4/03. Inspa		atureIV	*************	harage	-t-tames
: -p=	= sitton of Application: ∰ A ==:y: □'GMA □ □ UWCD	Approved with conditions  City	below 🗆 Denied	D	other	net manage of the manage of the little of the second	and the second of the second o	
Perm	it conditioned and checks	d by Barbara (	China	*************************	484	Dets 01/	28/03	
<u>CC</u> 1.	PUMP, motor, debris, removed from the we	, pollutants, and cont	aminants, Íncludin	g oil from	oll-lubricate	ed pumps,	shall be	
2.	Well casing shall be p 10 ft. of finish grade casing.	perforated over the de e. Perforations shall						
3.		material shall be appl grout pipe placed with				within 5 ft.	of finish	
4.	The Contractor shall a control channels, cree	retain all discharges v eks, rivers, sewers or			luids shall d	rain offsite	to flood	à.
5.	Casing shall be remove materials.	ved to a depth of 5 f	t. below finish gra	de, and v	vork area ba	ckfilled wit	th native	
6.	Public Works Inspector material. (NOTE: 24	or shall be present d <b>4-hour advance not</b>	uring casing perfo tice is required:	ration wo call (805	rk and place <b>) 654-290</b> 4	ment of a or 654-2	l sealing 2 <b>024.)</b>	
7.	All work shall be perf County.			the State	•			
	Peristin Minden Pilemen	Langus So	mounie		_	1/28/0	2.3	




#### County of Ventura WELL PERMIT APPLICATION 800 South Victoria Avenue, Ventura CA 93009

Page 2 of 2 Pages

Permit No. \_\_\_5331

#### LOCATION

INDICATE BELOW THE EXACT LOCATION OF WELL WITH RESPECT TO THE FOLLOWING ITEMS: PROPERTY LINES, WATER BODIES OR WATER COURSES, DRAINAGE PATTERN, ROADS, EXISTING WELLS, SEWERS AND PRIVATE SEWAGE DISPOSAL SYSTEMS, INCLUDE DIMENSIONS, LIST ASSESSOR'S PARCEL NUMBER AND THOMAS BROS, GUIDE NUMBER.




# WATER WELL SEALING RECORD

10 54340 AG1 70 MI PERMIT # 533 1

			31 JN 39"		FERIV	11 11 -0	351
RT DATE / 12	8,03		W 119°	13' 39.5"			
EXPIRATION DATE 7	128,03						
£3	(Vocare)		07115				
NEW WELL	DESTRU	ICTION [	OTHER	A PARTY AND	(Ante-		
TYPE OF MATER	IAL USED	Nest ceme	ot				
	DELIVERED TO SITE	LEFT OVER	USED FOR SEAUNO	BOREHOLE	WELL CASING	DEPTHO	SEAL
WELL#	Cu. Yd.	Cu. Yd.	Cu Yd	Diameter (NEW WELLS)	Diameter	FROM	TO
IST Jode!	7.0	0	7.0		12	228	25
D _ 20d lotd:	7.0	2 700 85	5.0				
O MIX ON SITE			1155 13.0				
O mixore							
METHOD OF SE			ROUT PIPE	☐ DROP	OTHER_		
NUMBER OF GR	OUT PIPE SE	ECTIONS	LENG	TH OF EACH	SECTION _2	0'	FEET
V		(DE	STRUCTION O	NLY)			
CONFIRMATION	THAT THE	CASING WAS F	IPPED OR PEF	REPORATED AS	REQUIRED BY	THE PE	RMIT.
· lack only	get knite	to 225: Pe	Broted han 3	25-20' Change	to conditions	verboly o	ppieue
		· - 10'595 «					
- I D VII BIED		- 10 595	s sperinees, "	7 COMPTER A			-4
DELIADIC.	A	21 - 11		"	0	1	
REMARKS:	onsite rulc	100 SAI	an well, re	guing cuthin	ot movete	To lema	re
• 7	if houth get	são karfe to de	oth Stated o	chroking of ~	13.00 = Comple	ed heets &	2=1430
· So	under death	before pedas 1430. Ist Huch 10	hors = 227' 6	Ale persona	d 222'		
DESCRIBE ANY	MARIANCE IN	1430 . Ist work to	EMETHOD OR	MATERIAL ERC	on DEBNIT CO	ISZO, DNIDITIOI	US OF
ANY OTHER FAC							
TO BE LESS THA							
			The state of the s				
IN MAY ORINION		SEALING WAS			The state of the s		
IN MY OPINION,		BEALING WAS:			INSPECTION SE	בחוווכבכ	
SATISFACTO	RY					HVICES	
			,		TART 100	711.	-
L.J UNSATISFAC	TORY FOR F	REASONS DESC	CRIBED ABOVE	. C	OMPLETED	540	-
OPTION:							
1							
		E AND IMMEDI	ATE VICINITY				
Y ATTACHED C	EMENT TRU	CK REPORT					
OTHER							
			M	N605		2/4/	03
DATE SEALED:	2 1 4	103		MEDERTOR	-	DV	

## **INSPECTION NOTES**

PERMIT # 5331





CEMXE F NANCIAL SERVICES L.P.

430 N. Vineyard Ave., Suite 500 • Ontario, CA 91764-4463 (909) 974-5500 • Fax (909) 974-5524

Azusa (21) 1201 W. Gladstone Compton (05) 2722 N. Alameda St. Hollywood (12) ORDER DESK 1000 N. La Brea

(800) 966-7796 Inglewood (06) 505 Railroad Pl

CX04514 (4/01)

Irvine (09)

16161 Construction Circle E

Los Angeles (14) 625 Lamar

Moorpark (42) 9035 Reseland Ave. Orange (31) 1730 N. Main St.

S. J. Capistrano (01) 31601 Ortega Hwy

Santa Paula (44) 1430 Santa Ciara Simi Valley (43)

8960 Bradley

Walnut (04) 20903 Courier Rd

1092781

1.49PM

300 W. Les Angeles Ave.
Sun Valley (10) Online France 748915

DATE	LEAVEPLANT	ARRIVE JOB	START UNLOAD	PINISIFUNLOAD	LEAVE JOB	ARRIVE PLANT	STANDING TIME
PLANT/ALLEY	SALESMAN		ORDER NO	ENTERFO BY	APPLICATION		
CEMENT	FLYASH	W/C SAND	WE ROCK	PROCK	LIQ" ROCK	LWTSAND	CU FI LWT AGG
JALS FREE MOIST	GALS ADDED	MAX GALS, ALLOW	GALS ADDED ON			P SLUMP SLUMP L L CYL CYL CYL L JIN MIDDLE EN	300
CUNTOMER P.O.	Cus	STOMER JOB NO	ZONE MIDDLE	MAP PAGE	TIME TRUCK	DRIVER	
USTOMER NAME	A DRILLIN	G ENC.	CUSTOMER NO		SPECIAL INSTRUCTIONS		TDE
DELIVERY ADDRESS	PALMAS &	OCEAN	PROJECT NO		B05-797-423	a	
CROSS STREETS			TOTAL ORDERED	TOTAL SHIPPED			
LOAD# QUANTITY	Y UOM	MIX NQ. 31	UMP	PRODUCCOESCRIP	TION	UNITPRICE	EXTENSION
andusta.	Talge	Setual	Shatus			ENVIRONMENTAL	
	700					BALANCE FORWARD	
2/4/0	3 61	Luckbad.				MINIMUM LÖAD	
1-7-	157	Nuck bad				SALES TAX	
					1	SUB-TOTAL	
MENT	12852 []	man	In tal			STANDING TIME	
APER *	( 865 B)	1 686	In Tel	F & had		TOTAL	
		7/4/63	- 2pd	SVC EX 1000	MSD	CHARGE	COD
veighmatter, whose signrescribed by Chapter	at the following described gnature is on this certific 7 (commencing with Sect administered by the Do	ER CERTIFICATE  I commodity was weighed, eate, who is a recognized tion 12700) of Division 5 vision of Measurement St	authority of accuracy, as of the California Business		VN JOB NOT RE	harged at the prevailing r	
Oeputy 1 1 1	MARCADO	i / IX					
Received by and	WIVE	AL VA	12				

**INSPECTOR** 



430 N. Vineyard Ave., Suite 500 • Ontario, CA 91764-4463 (909) 974-5500 · Fax (909) 974-5524

Azusa (21) 1201 W. Gladstone Compton (05) 2722 N. Alameda St.

Hollywood (12) 1000 N. La Brea Inglewood (06) 505 Railroad Pl

ORDER DESK (800) 966-7796

CX04514 (4/01)

Irvine (09) 1616) Construction Circle E

Los Angeles (14)

Moorpark (42) 9035 Roseland Ave. Orange (31) 1730 N. Main St

S. J. Capistrano (01) 31601 Ortega Hwy Santa Paula (44)

1430 Sania Clara

Sun Valley (10) 8960 Bradley

TICKET OPPROO Walnut (04) 20903 Courier Rd

DATE OF THE STATE OF	門門的	ARBUTE JOB O	START UNLGAD	1530	LEAVE JOB	ARRIVE PLANT	STANDING TIME
PLANTIALLEY	SALE MAN		ORDER NO	ENTERED BY	APPLICATION	1	
CEMENT	FLYASH	W/C SAND	3/8" ROCK	I ROCK	1 1/2" ROCK	LWT SAND	CUFT LWT AGG
GALS FREE MOIST	GALS ADDED	MAX GALS, ALLOW	GALS ADDED ON BEGIN MIDDLE	IOB ORU		AP SLUMP SLUMP CYL CYL	
CUSTOMER P O	cus	TOMER JOB NO.		MARPAGE 14	TIME 1 1/2 TRUCK /		
CUSTOMER NAME	S BRILLIN	A XBVCZ	CUSTOMER NO		ANGCIAL MATRUPTIONS!		IDE
DELIVERA VODRERA	s palmas a	CHIEFRE	PROJECT NO.				
CROSS STREETS			TOTAL ORDERED	TOTALSHIPPED			
OAD # QUANTIT	Y 1 YUOM (14)	ALDENIS ISL	unit I Livi CE	Dibrobuct descri	PTION	UNIT PRICE	EXTENSION
	2/4/0	3 - 2na	Luck loca		1000	BALANCE FORWARD MINIMUM LOAD	
	2/4/03 - 2nd truck load. MSD					SALES TAX	- Y
EMENT	10060 11	12820	No Tal			SUB-TOTAL.	
ENEXT.	ASSESSED IN	J: Singhaw	10 192			STANDING TIME	
ATER s	1 666 6	1 865	In Tel		F	TOTAL	
	-					CHARGE	COD
weighmaster, whose si- prescribed by Chapter and Professions code. Department of Food and	at the following described gnature is on this certific 7 (commencing with Sect administered by the Dis	ER CERTIFICATE commodity was weighed, ale, who is a ronognized ton (2700) of Division 5 distant of Measurement Sta	authority of accuracy, as of the California Business		WN DIOB NOT R	charged at the prevailing r	
Received by and terms agreed to X	VKE	SYVW		Air			1 4 1

INSPECTOR



Perbishing wsing



flunging 1st tockbod ofcement



Mills Knike

( Permit 5331 - 2/4/03 des)



I fumping and fuch load of cement



Completed seel - cenent of top of cesing, under ~17" when



Appendix G

**Report Figures** 



Reference: Google Earth 2018



No Scale




SITE LOCATION MAP

C.I. BEACH 112 Las Palmas Steet Oxnard, California

Client # 4844 Report # 10139

FIGURE 1



## **EXPLANATION**



Approximate Location of Exploratory Boring



Scale: 1" = 20'





**EXISTING SITE PLAN** 

C.I. BEACH 112 Las Palmas Steet Oxnard, California

Client # 4844 Report # 10139

FIGURE 2







Scale: 1" =  $\frac{1}{4}$  mile



SEISMIC HAZARD ZONES MAP C.I. BEACH 112 Las Palmas Steet Oxnard, California

Client # 4844 Report # 10139

FIGURE 4